


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

2-13-10E

Company - SKELLY OIL CO.
Farm - Carl Thowe No. 4
Thowe (Small)

SEC. 2. T. 13 R. 10E
SW NE SE
990' fr N.L. 1050' fr E.L.
SE/4
County. Wabaunsee
KANSAS



Total Depth. 2934 PB 2925
Comm. 12-18-50 Comp. 1-1-51
Shot or Treated.
Contractor. Adkins Drlg. Co., Inc.
Issued. 8-4-51

CASING:

8 5/8" 202' cem. w/175 sx
5 1/2" 2930' cem. w/135 sx

Elevation. 1102 DF

Production. 1156 BOPH 24/hrs.

Figures Indicate Bottom of Formations.

shale, sand & lime	210
shale & shells	600
shale & lime	1368
lime	1582
shale & lime	1700
lime, shale & sand	2194
lime & chert	2458
lime	2488
shale	2684
lime & chert	2703
lime	2852
shale & lime	2930
lime	2934
Total Depth	

Tops:	
Howard	584
Topeka	648
Lansing	1223
Kansas City	1368
Miss. Lime	2198
Kinderhook	2488
Hunton	2684
Maquoketa	2852
Viola	2930

Measurements from top of rotary
drive bushing to ground level 5'.

1-20-51 Shot with 250 gal. between
2930-2934'

Good porosity and sat. 2930-2933'

Attempted DST: #1 2929'-2933';

Tool failed to open.

DST: #2 - 2929'-2933'; Tool open

1 hr. & 35 min.; rec. 30' clean

oil and 5' oil cut mud. Bottom

hole shut in pressure after 15

min. 1100#.

Ran Schlumberger Survey to 2933'

Producing formation - Viola Lime
2930'-2934'

RTD 2933