

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


36-13-11E

Company- PHILLIPS PET.
Farm- Hughes "D" No. 1

SEC. 30 T. 13 R. 11E
App 25' E NE NW

Total Depth. 3579'
Comm. 1-3-64 Comp. 1-23-64
Shot or Treated.
Contractor. White & Ellis Drlg.
Issued. 2-15-64

County Wabaunsee
KANSAS



CASING:

10" 303' cem w/ 225 sx

Elevation. 1422' DF

Production. DRY

Figures Indicate Bottom of Formations.

soil	5
lime	40
limed shale	160
lime hard	180
lime	311
lime w/sh. le streaks	480
shale & lime streaks	834
shale & shells	897
lime & shale	1030
lime & shale streak	1085
lime & shale	1220
shale	1272
lime	1315
sand	1521
shale & lime	1570
lime w/shale streaks	1730
lime	1935
lime & shale	1994
lime & shale streaks	2073
lime & shale	2140
shale	2190
sand	2224
lime & shale	2365
shale w.lime streak	2445
shale & lime	2555
chert	2569
shale	2586
sand	2622
lime	2941
shale	3118
lime	3302
shale	3344
lime	3388
sand	3396
shale & lime	3451
shale w/ dolomite & sandy chert	3492
sand & dolomite	3514
shale & sand	3557
Total Depth	3579 RTD

Total Depth

Formations:

Lansing	1568
Kansas City	1570
Base Kansas City	1908
Marmaton	2026
Cherokee	2130
Mississippi	2607
Kinderhook	2939
Hunton	3118
Maquoketa	3266
Viola	3344
Simpson shale	3431
Simpson Dolomite	3434
Simpson Shale	3450
Arbuckle	3557