


Company

Sec. 29 or T. 13 R. 21 E
Loc. 32

Farm F. Gerstenberger No. 2

29-13-21E Plotted
County DouglasTotal Depth 1104
Comm. About 1903
Shot or Treated
Contractor
Issued

Comp.



Casing

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation

Production Dry

Figures Indicate Bottom of Formation

soil	8
lime	11
gravel	13
lime	19
shale	27
shale	47
lime	85
shale	104
lime	150
shale	179
lime	193
shale	196
lime	200
shale	215
lime	227
shale black	232
shale	240
lime	252
shale	262
lime hard	277
lime	289
shale	294
lime	339
shale	347
sand gas	353
shale	385
lime	390
shale	435
lime	441
shale	476
sand gas & oil	481
shale	491
lime	497
shale	535
lime	540
shale blk wtr	544
lime	558
shale	586
lime	590
sand gas & oil	600
shale	665

sand gas	690
shale	805
sand gas	839
shale black	870
sand gas & oil	890
shale black	914
shale	1030
lime	1045
sand gas	1070
sand wtr	1075
lime Miss.	1104

Total Depth.

Available records show location as SW 32-13-21 C. C. Gerstenberger and Brother Homer say this is log of well at CEL SE NW 29-13-21E and that no well was ever drilled in section 32.

Carl Gerstenberger says that this well was about 1000 feet north of the SE corner of the NW $\frac{1}{4}$ section 29-13S-21E and near the east line.

Harry Brown with Frank Black says that at 839 they would have had a mighty good gas well but were looking for oil.

Carl says that about 1934 he located the old hole, dug off the dirt, removed a rock and uncovered the drive pipe, that the hole was full of water but that the gas was boiling the water a plenty.

835
339
496