

Question on Location
of well

30-13-22E

35715

Chas. E. Schwab #1
Sec. 30-13-22
Johnson County, Ks.

Section doesn't fit

135-22E

Casing Record.

6 5/8" 1764 1/2
5 3/16" 2131

Soil soft		5	water sand	10	1370
light lime hard	25	30	lime hard	5	1375
light shale soft	50	80	shale light soft	25	1400
light lime hard	5	85	shale black	5	1405
light shale soft	25	110	shale light	35	1440
lime hard	10	120	lime light	5	1445
shale soft	60	180	shale light	60	1505
lime hard	10	190	very little water		
shale soft	50	240	sand black	15	1520
lime hard	5	245	shale light	240	1760
shale soft	55	300	lime light	4 1/2	1764 1/2
lime hard	15	315	sand light lime	60 1/2	1825 H2O
shale soft	35	350	sand light	13	1838 more H2O
lime hard	30	380	lime hard	52	1890 " "
shale soft	10	390	sand light	50	1940 " "
lime hard	5	395	sand gray	50	1990 " "
shale soft	50	435	sand light	5	1995 " "
lime hard	10	445	sand light	105	2100 " "
shale soft	20	565	shale light	30	2130
lime hard	10	575	lime	23	2153
water sand soft H2O	20	595	lime soft	7	2160
shale blue mud	40	635	showing of oil		
shale sandy soft	35	670			
lime light hard	25	695	Sand - like rubber.		
shale dark soft	10	705	Sand Hole full water	2162	
light lime hard	20	725			
shale light soft	10	735			
lime light hard	35	770			
shale light soft	10	780			
lime gray hard	20	900			
water sand gray	15	915			
lime light hard	20	945			
shale dark soft	10	955			
lime light hard	5	960			
shale dark soft	20	980			
lime light hard	70	1050			
shale hard soft	5	1055			
lime light hard	10	1065			
sand light soft	20	1085			
lime light hard	5	1090			
shale soft	5	1095			
lime light hard	15	1110			
shale soft	10	1120			
lime hard	5	1125			
shale soft	120	1245			
lime hard	15	1260			
shale soft	15	1275			
lime hard	25	1300			
shale soft	30	1330			
lime hard	10	1340			
shale soft	10	1350			
lime hard	10	1360			

From Peerless Oil Co. Ottawa, Kansas.