

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


33-13-224

F. J. KASPER
Kaths No. 2.

SEC.33 T.13 R.22E
Sec NW

Total Depth. 782' PB 665'
Comm. 4-6-40 Comp. 6-5-40
Shot or Treated.
Contractor. Gatton Drlg.Co.
Issued. 7-13-40

County. Johnson



CASING:

Elevation. 930

Production. 180,000 Gas.

Figures Indicate Bottom of Formations.

soil red & clay	3	shale dk	635
lime boulder	15	sand, gas 180,000	646
shale gy	32	shale gy	652
lime gy	59	shale gy dk	660
shale gy	60	lime sdy	664
lime	93	shale	671
shale	94	sand	674
lime	99	shale gy	680
shale gy	142	shale dk slaty	691
lime	154	shale gy	761
shale dk	159	sand, sh gas	765
shale gy	164	shale dk sdy	770
lime sdy sft	166	shale dk	775
lime hrd	178	wtr sand	782
shale dk	183 ¹ / ₂	Total Depth.	
lime	184		
shale gy	192	Plugged back 665, com-	
lime	215	pleted as gas well	
shale gy	218		
lime	220		
shale slatey	229		
lime	237		
shale	238		
lime	254		
shale & slate	260		
lime (Bethany Falls?)	284		
shale & slate	286		
lime hrd	294		
shale gy	297		
lime (Base Hertha)	304 (4621)		
shale gy	410		
shale gy sdy	425		
shale gy	446		
red bed	447		
shale gy	453		
lime	456		
shale gy	457		
sand	463		
shale gy sdy	475		
lime	480		
shale dk	483		
lime	486		
shale gy	495		
lime	504		
shale dk	517		

lime	521
slate	523
shale gy sdy	528
limy sand	537
shale gy	540
shale dk	545
shale gy	548
lime	550
shale gy sdy	555
sand hrd	561
shale green	562
sand	583
shale gy	610
shale dk	614
lime brown	616