

16-13-23 E 9.2-8. 0

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


UNION GAS COMPANY,
May Summit No. 1

SEC. 16 T. 13 R. 23E.
CNW SE

Total Depth. 703'1"
Comm. ? Comp. ?
Shot or Treated.
Contractor.
Issued. 2-11-39

County Johnson.

FEB 11 1939



CASING.

8 1/4" 18'6"
6 3/4" 409'
47/8" 574'

Elevation. 947 L.S.

Production. 40,000 G.

Figures Indicate Bottom of Formations.

shells and lime	14
shale	18
lime	45
shale	93
lime	102
shale	116
lime and shale	
breaks	131
shale	149
lime	169
shale muddy	173
lime	187
shale	189
lime	205
shale	212
lime	231
shale	235
lime	238
shale	243
lime	249
shale	284
sand	355
shale	363
lime sdy	365
shale	386
red rock	391
shale	395
lime	397
shale	406
lime	409
sand	410 gas
sand	425
shale	427 1/2
shale	431
lime	435
shale	449
lime	454
shale	472
lime	477
shale	483

lime	527
shale	529
sdv lime	537 36,000 Gas.
sand	543 40,000 Gas.
Total Depth.	

DEEPEMED.
Sagamore Oil and Gas Co.
Comm. 6-3-36 Comp. 6-11-36
Prod. Dry.
shaley sand 569'2"
shale 594
shale sdy 606
shale 629
lime 631
shale 690
lime 692
shale 703'1"

Total Depth

23,000 gas	413 1/2
20,000 gas	416 1/2
20,000 gas	420
24,000 gas	424
20,000 gas	427 1/2

sdv lime	485
shale sdy	493
sdv lime	495
red rock	502
shale	505
lime	506
shale	526