

Company

Farm C. A. Hyer

No. 1

Sec. 36

T. 13

R. 23E

Loc. City of Olathe
SW SE NW?

County Johnson

Total Depth 371'


Comm. 9-30-29

Comp. 10-3-29

Shot or Treated

Contractor Earl Smith

Issued



Casing

20 in.	10 in.	
15 1-2	8 1-4	
12 1-2	6 5-8	348'
13 3-8	5 3-16	

Elevation

Production

Figures Indicate Bottom of Formation

Soil	5'	Shale - dark	313
Sand rock	7	Lime	335
Yellow clay	10	Shale	338
Lime	29	Lime	341
Shale - dark	35	Shale - blue	346
Lime	41	Lime	355
Shale - light	52	Shale - white	361
Lime	65	Sand - gas	369
Shale	86	Shale - light	371
Lime	124		
Shale-light blue	186		
Lime - shale breaks	20-2		
in first 9 ft.			
Shale - dark-	212		
Shale - light	218		
Lime	225		
Shale - white	230		
Lime	238		
Shale	269		
Lime	270		
Shale	277		
Lime	307		

Open flow test	40,000
Rock Pressure	90 lbs.

cleaned

Red out Hole Oct. 20, 1936.

Set 2 " tubing 22 ft. of 28" Anchor to bot. of 6 1/4 P. Rubber.

Set 1 " " 27 ft. of 1" Anchor to bot. of Pony P. Rubber.

Each cage just under Packers.