

Form 113 50M 4-49-47450-D

State Kansas County Wabaunsee (W)

Sec. 33 Twp. 13 Rng. 10a Elev. 1120

Company Carter Oil

Well No. 1 Name O. H. Davis

Location SW SE SW

Feet from lines: N. S. E. W.

Spud 1-1-19 Completed 6-1-19

T. D. 3206 Casing 7" 3201

Comp. Perf.

Pay 3201-06 in Viola

I. P. 2580 BOPD

Choke T. P. C. P.

G. O. R. Grvty.

DATE	REMARKS
6-1-19	Top. 952, Heeb. 1262, Lans. 1520, B-KC 1889, Cherokee 2104, Miss. 2474, Kind. 3810, Hunt. 2973, Maq. 3121, Viola 3199, strk. 80 1846-

DATE	REMARKS
	56. DST 1843-59, open 1 hr.,
	30 min., rec. 20' free oil
	& 70' heavy OCH. MP 250#
	Ø 1859-69, rec. 6' lm., 4" dens
	lm., 5" blk.ch., 9" dense lm.,
	2' blk.sh., 6" gr. green sh.
	sd. NS 2153-93, lm. 2194-2200
	tr. FO, fairly spt. lm. 2211-17
	Ø 2217-20, rec. 3' dk.gr.sh.,
	gd.por., NS,
	Ø 3202-06 RTD, rec. 2' 3" sat.
	dolo. 14" crs. X dolo., gd. sa
	& por., 13" spt.por., gd. sat.
	DST 3201-06, open 1 1/2 hrs.,
	rec. 1900' oil, no wtr.
	Grav. 29, Ran Schlum.
	DP TD Swb/54 BO/6, 1500' off
	btm., 2% BS, no wtr., Swb/100
	BO/4 hr. 2% mud,
	P/500 BO / 2% mud/50 hrs.
	last 20 hr., P/129.05 BO @
	20, 38" strks.per minute.
	Echo.pot. 2580 BOPD, no wtr.
	COMPLETE
	LOGS 113 20M 4-5-64 PCD