

8-13-8E
SE NW SE ✓

Elev. 1509' KB

CASING RECORD

10 3/4"

197' Cemented
w/200 sacks

Total Depth

2855'

Location: SE NW SE

Section: 8-13S-8E

Geary County, Kansas

Farm: Glessner #1

Well Owner: E. N. Brockman, Etal

Contractor: WHITE & ELLIS DRILLING, INC.

Commenced: 10-29-70


Completed: 11-5 -70

KELLY BUSHING MEASUREMENT 5' ABOVE GROUND LEVEL

FORMATION	DEPTH
Cellar	0-10
Clay	25
Lime	95
Shale & Lime	135
Lime & Shale	400
Shale w/Lime (Stks.)	1300
Shale & Sandy Shale	1450
Sand	1507
Lime	1580
Lime & Shale	1820
Lime	1838
Shale & Lime Stks.	2040
Shale & Lime	2280
Lime & Shale	2288
Lime	2405
Lime w/Shale (Stks.)	2479
Lime	2606
Lime & Dolomite	2710
Lime & Shale	2838
Lime	2855

TOPS

Lansing	1507
Kansas City	1820
Hunton	2288
Viola	2479
Arbuckle	2838



DRY HOLE

ark
PLUGGED & ABANDONED

Log Tops

Oread	1310
Douglas	1460
Lansing	1548
B. Kansas City	1840
Cherokee	1982
Kinderhook	2056
Hunt	2286
Mag.	2522
Viola	2607
Simpson	2674
Ed.	2713
Arbuckle	2795