

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

23-13-85

Company- CONTINENTAL OIL COMPANY

Farm- H. R. Falk

No. 1

SEC. 23 T. 13 R. 8E

SW SW NW

2310' fr N. & 330' fr WL, NW $\frac{1}{4}$

(Stratt Test N. AA-130)

Total Depth. 2400


Comm. 1-14-53

Comp. 1-27-53

Shot or Treated.

Contractor.

Issued. 2-14-53

County Wabaunsee
KANSAS

CASING:

8 5/8" 253'

Elevation. 1497 RB

Production. Dry

Figures Indicate Bottom of Formations.

shale & lime	150
lime	290
shale & lime	1245
sand & shale	1435
lime & shale	1500
sand	1530
lime	1560
lime & shale	1590
lime	1615
shale	1625
lime	1685
lime	1740
shale	1750
sand	1785
shale	1830
lime & shale	1890
sand & shale	1950
lime	2080
shale	2100
dolomite & shaley	
dolomite	2170
dolomite & lime	2240
shale	2245
sandy dolomite &	
lime	2270
sand & shale	2280
sand	2330
sand & shale	2365
dolomite	2400
Total Depth	

Sch. Tops:

Lansing	1434
Kansas City	1530
Base-Kansas City	1740
Hunton	1948
Maquoketa	2082
Viola	2170
Simpson	2271
Arbuckle	2365

DST: 1645-1655' open 1 1/2

hrs. weak blow for 18 mins.

Intermittent weak blow for

rest of test. Rec. 8' mud

60' salty mud, and 60' muddy

salt water with few spots of

oil. BHP 460#.

Cored Simpson 2292-2302'. rec.

6' sand, fair porosity, no

stain.