

KANSAS

24-13-9E

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 County Number

S. 24 T. 13S R. 9 E
Loc. SE NW
County Wabaunsee

Operator
St. Michael Exploration Company

Address
610 FNB Bldg. Abilene, Texas 79601


Well No. #1 Lease Name Fink

Footage Location
1980 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor EDCO Drilling CO. Geologist Roberto Yanez

Spud Date 11/7/79 Date Completed 11/15/79 Total Depth 3430 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser Dry Hole



Locate well correctly
Elev.: Gr. 1259
DF KB 1263

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	20	150	Class C	80	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None					

Size	Setting depth	Packer set at
None		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans- mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

St. Michael Exploration Co.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Dry Hole

Well No.

#1

Lease Name

Fink

S 24 T 13 SR 9 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Rock and Soil	30	82		
Lime and Shale	82	146		
Surface Hole	146	165		
Shale	165	677		
Shale with Lime Streaks	677	850		
Shale with Lime	850	1090		
Lime	1090	1390		
Shale with Lime	1390	1524		
Shale with Lime Streaks	1524	1775		
Kansas City Lime	1775	1994		
Lime with Shale Streaks	1994	2395		
Shale with Lime Streaks	2395	2536		
Lime	2536	2682		
Shale with Lime Streaks	2682	2716		
Chattanooga Shale	2716	2778		
Lime	2778	2965		
Lime with Shale Streaks	2965	3125		
Lime	3125	3226		
Muskgokee Shale	3226	3310		
Viola	3310	3406		
Lime	3406	3414		
Shale	3414	3430		
Arbuckle R.T.D.	3430			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Wanda Weaver
Signature

Owner
Title

Mar 30, 1981
Date

51-12-2E