

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


29-14-12E

Company- NATURAL GAS & OIL CO.
Farm- Harrold No. 3

SEC. 29 T. 14 R. 12E
C NW NE

Total Depth. 3126'
Comm. 8-20-59 Comp. 8-30-59
Shot or Treated.
Contractor. Twin Drlg, Inc.
Issued. 12-5-59

County Wabaunsee
KANSAS



Elevation. 1391' R.B.

Production. 96 BOPD

CASING:
8 5/8" 220' w/200 sx cem.
5 1/2" 3123' w/175 sx cem.

Figures indicate Bottom of Formations.

shale	20
lime, shale	221
shale	250
shale, lime shells	1025
shale, lime	1602
lime	1660
lime, shale	1995
shale, sand	2080
shale, lime	2275
shale	2392
shale, sand	2426
lime	2533
lime, chert	2590
lime	2692
lime, shale	2901
lime	3114
lime, sand	3124 RTD
lime, sand	3126
Total Depth	

TOPS:

Howard	697
Topeka	737
Oread	1041
Lansing	1346
Kansas City	1522
B/Kansas City	1719
Mississippi	2426
Kinderhook	2721
Hunton	2867
Viola	2992
Simpson Dolomite (Scout)	3102
Simpson sand	3120

D.S.T. #1 - 2034-80', open 1 hr.
Rec. 5' mud. IBHP 60#/20", IFP
20#, FFP 40#, FBHP 50#/15".