


S. 30 T. 14S R. 12 ^E

Loc. C SW SW SW

State Geological Survey
WICHITA, BRANCH

DF _____ KB _____



Locate well correctly

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 $\frac{1}{4}$ "	8-5/8"		201'	Common	125	3% CC
PRODUCTION							

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Formation	Top	Btm.	Formation	Top	Btm.	Formation	Top	Btm.
Soil	0	6						
Shale	6	15						
Lime w/shale stk	15	200						
Shale w/lime stk	200	690						
Lime w/shale	690	807						
Shale	807	824						
Lime	824	828						
Shale w/lime stk	828	963						
Lime	963	993						
Shale	993	1146						
Shale w/lime stk	1146	1268						
Lansing Lime	1268	1442						
K. C. Lime	1442	1648						
Base K. C.	1648	1768						
Marm.	1768	1821						
Lime	1821	1828						
Shale	1828	2330						
Mississippi	2330	2645						
Kinderhook	2645	2790						
Hunton	2790	2928						
Viola	2928							

MISCH—COFFEYVILLE