

SIDE TWO

Operator Name Rolex, Inc. Lease Name Lawson Well# 7 SEC 15 TWP. 14 RGE. 20 ☒ East ☐ West

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☐ Yes ☒ No
 Samples Sent to Geological Survey ☐ Yes ☒ No
 Cores Taken ☒ Yes ☐ No

Formation Description
☐ Log ☒ Sample

Core 671-683

Name	Top	Bottom
Sandy Shale	553	570
Lime	570	575
Shale	575	591
Lime	591	599
Sandy Shale	599	613
Lime	613	615
Shale	615	630
Lime	630	632
Shale	632	648
Lime	648	649
Shale	649	660
Sandy Shale	660	662
Lime	662	663
Sandy Shale	663	667
Lime	667	668
Sand	668	678
Sandy Shale	678	725

T.D.

Name	Top	Bottom
Soil & Sandy Clay	0	47
Lime	47	63
Shale	63	74
Lime	74	80
Shale	80	87
Lime	87	108
Shale	108	139
Lime	139	161
Shale	161	220
Lime	220	223
Shale	223	248
Lime	248	250
Shale	250	262
Lime	262	270
Shale	270	278
Lime	278	305
Shale	305	309
Lime	309	311
Shale	311	324
Lime	324	345
Shale	345	349
Lime	349	350
Shale	350	375
Lime	375	385
Shale	385	401
Lime	401	405
Shale	405	408
Sandy	408	441
Lime	441	442
Shale	442	458
Sandy Shale	458	526
Shale	526	550
Lime	550	553

CASING RECORD

☒ new ☐ used

Report all strings set - conductor, surface, intermediate, production, etc.

Purpose of string	size hole drilled	size casing set (in O.D.)	weight lbs/ft.	setting depth	type of cement	# sacks used	type and percent additives
surface	10"	7"	16½	40	Portland	10	none
production	6½"	2 7/8"	6½	698	V-cements	170	none

PERFORATION RECORD

shots per foot specify footage of each interval perforated

2 671-676 w/11 shots

Acid, Fracture, Shot, Cement Squeeze Record

(amount and kind of material used)

frac 4000# SD & 100 bbls oil

Depth

671-676

METHOD OF COMPLETION

Disposition of gas: ☒ vented☐ sold☐ used on lease☐ open hole ☒ perforation☐ other (specify)☐ Dually Completed.☐ Commingled

PRODUCTION INTERVAL

671-676