

CORE ANALYSIS REPORT

FOR

J. C. BROWN  
J. C. BROWN NO. 3-B WELL  
DOUGLAS COUNTY, KANSAS

CORE LABORATORIES, INC.  
*Petroleum Reservoir Engineering*  
TULSA, OKLAHOMA

May 2, 1985

REPLY TO  
7304 EAST 38TH STREET  
TULSA, OKLAHOMA  
74145

J. C. Brown  
Rural Route 3  
Baldwin, Kansas 66006

Attn: Mr. J. C. Brown

Subject: Core Analysis Data  
J. C. Brown No. 3-B Well  
Douglas County, Kansas  
CLI File 3408-850072

Gentlemen:

Cores taken in the subject well in the Squirrel Sand formation were received at the Tulsa laboratory for special analytical testing described on the Procedure Page.

The accompanying Coregraph presents binomially averaged core analysis data in graphical form to aid correlation with downhole electrical surveys.


Tabular presentation of the measured physical properties may be found on page one of this report.

Empirical estimates of stock tank oil in place may be found on page two.

It is a pleasure to have this opportunity of serving you.

Very truly yours,

CORE LABORATORIES, INC.



J. Michael Edwards  
District Manager

JME:ja

5 cc - Addressee  
1 cc - Kansas Land Investment, Inc.  
Attn: Mr. Jim Mietchen  
222 East 3rd  
Ottawa, Kansas 66067

J. C. Brown  
J. C. Brown No. 3-B Well  
CLI File 3408-850072

Procedure Page

#### Handling and Analytical Procedures

Diamond coring equipment and air were used to obtain 2-1/8 inch diameter cores between 679.0 and 689.3 feet.

The cores were preserved at the well site in plastic bags by client representative.

The cores were transported to Tulsa by bus.

Plug analysis was made in intervals requested.

Fluid removal was accomplished using high temperature retorts.

Porosity was determined by summation-of-fluids technique.

Horizontal air permeability on plugs measured without Klinkenberg correction.

Temporary storage of cores in Tulsa laboratory for a period of thirty days without additional charge.

J. C. BROWN  
 J. C. BROWN NO. 3-B WELL  
 DOUGLAS COUNTY, KANSAS

DATE : 5-2-85  
 FORMATION : SQUIRREL SAND  
 DRLG. FLUID: AIR  
 LOCATION :

FILE NO. : 3408-850072  
 API NO. :  
 LABORATORY: TULSA, OKLAHOMA

CONVENTIONAL PLUG ANALYSIS

SAMPLE NUMBER	DEPTH FEET	PERM PLUG	FLD POR	OIL% POR	WTR% POR	DESCRIPTION
1	679.0-80.0	2.0	18.1	27.8	47.6	SD FN GRN CALC MICA SLTY
2	680.0-81.0	146.	20.7	25.3	37.4	SD FN GRN CALC MICA
3	681.0-82.0	40.	18.5	32.4	28.6	SD FN GRN LMY MICA
4	682.0-83.0	21.	21.4	32.5	33.6	SD FN GRN SL/CALC SH LAMS MICA
5	683.0-84.0	19.	21.6	35.1	31.0	SD FN GRN SL/CALC SH LAMS MICA
6	684.0-85.0	47.	22.0	36.4	30.3	SD FN GRN SL/CALC MICA
7	685.0-86.0	41.	21.9	31.4	34.5	SD FN GRN SL/CALC MICA
8	686.0-87.0	0.73	14.5	10.0	70.3	SD FN GRN V/SLTY SL/CALC MICA SHY
9	687.0-87.5	12.	20.1	33.5	40.5	SD FN GRN SL/CALC SH LAM MICA
	687.5-88.0					SH
10	688.0-89.0	18.	19.3	37.7	40.1	SD FN GRN SL/CALC SH LAM MICA
	689.0-89.3					SD SHY

*h = 7.5*  
*φ = 20.7*  
*S<sub>o</sub> = 33*  
*S<sub>w</sub> = 34.1 (30.5)*  
*∑ = 628*

These analyses, opinions or interpretations are based on observations and materials supplied by the client to whom, and for whose exclusive and confidential use, this report is made. The interpretations or opinions expressed represent the best judgment of Core Laboratories, Inc. (all errors and omissions excepted); but Core Laboratories, Inc. and its officers and employees, assume no responsibility and make no warranty or representations, as to the productivity, proper operations, or profitability of any oil, gas or other mineral well or sand in connection with which such report is used or relied upon.

**CORE LABORATORIES, INC.**  
*Petroleum Reservoir Engineering*  
 DALLAS, TEXAS

Page 2

J. C. BROWN  
 J. C. BROWN NO. 3-B WELL

DATE : 5-2-85  
 FORMATION : SQUIRREL SAND

FILE NO. : 3408-850072  
 ANALYSTS : HUDSON

\*\*\* CORE SUMMARY AND CALCULATED RECOVERABLE OIL \*\*\*

DEPTH INTERVAL: 679.0 TO 686.0

FEET OF CORE ANALYZED : 7.0 FEET OF CORE INCLUDED IN AVERAGES: 7.0°

-- SAMPLES FALLING WITHIN THE FOLLOWING RANGES WERE AVERAGED --

PERMEABILITY HORIZONTAL RANGE (MD.)	:	0.10 TO 150.	(UNCORRECTED FOR SLIPPAGE)
FLUID POROSITY RANGE (%)	:	10.0 TO 100.0	
OIL SATURATION RANGE (%)	:	10.0 TO 40.0	
WATER SATURATION RANGE (%)	:	20.0 TO 80.0	

SHALE SAMPLES EXCLUDED FROM AVERAGES.

AVERAGE PERMEABILITY (MILLIDARCIES)		AVERAGE TOTAL WATER SATURATION	:	34.5
ARITHMETIC PERMEABILITY	:	(PERCENT OF PORE SPACE)		
GEOMETRIC PERMEABILITY	:			
HARMONIC PERMEABILITY	:			
		AVERAGE CONNATE WATER SATURATION	:	(C) 30.8
		(PERCENT OF PORE SPACE)		
PRODUCTIVE CAPACITY (MILLIDARCY-FEET)				
ARITHMETIC CAPACITY	:	OIL GRAVITY (API)	:	(E) 34.0
GEOMETRIC CAPACITY	:			
HARMONIC CAPACITY	:	ORIGINAL SOLUTION GAS-OIL RATIO	:	(E) 1.
		(CUBIC FEET PER BARREL)		
AVERAGE POROSITY (PERCENT)	:	ORIGINAL FORMATION VOLUME FACTOR	:	(C) 1.05
		(BBLS SATURATED OIL/STOCK-TANK BBL)		
AVERAGE RESIDUAL OIL SATURATION	:			
(PERCENT OF PORE SPACE)	:	ORIGINAL STOCK-TANK OIL IN PLACE	:	(C) 1053.
		(BARRELS PER ACRE-FOOT)		

=====

CALCULATED MAXIMUM SOLUTION GAS DRIVE RECOVERY IS \_\_\_\_\_ BARRELS PER ACRE-FOOT, ASSUMING PRODUCTION  
 COULD BE CONTINUED UNTIL RESERVOIR PRESSURE DECLINED TO ZERO PSIG. CALCULATED MAXIMUM WATER DRIVE  
 RECOVERY IS \_\_\_\_\_ BARRELS PER ACRE-FOOT, ASSUMING FULL MAINTENANCE OF ORIGINAL RESERVOIR PRESSURE  
 100% AREAL AND VERTICAL COVERAGE, AND CONTINUATION OF PRODUCTION TO 100% WATER CUT.

=====

(C) CALCULATED      (E) ESTIMATED      (M) MEASURED      (\*) REFER TO ATTACHED LETTER.



COMPANY J. C. BROWN FILE NO. 3408-850072  
 WELL J. C. BROWN NO. 3-B WELL DATE 5-2-85  
 FIELD \_\_\_\_\_ FORMATION SQUIRREL SAND ELEV. \_\_\_\_\_  
 COUNTY DOUGLAS COUNTY STATE KANSAS DRLG. FLD. AIR CORES \_\_\_\_\_  
 LOCATION \_\_\_\_\_

# CORRELATION COREGRAPH

These analyses, opinions or interpretations are based on observations and material supplied by the client to whom, and for whose exclusive and confidential use, this report is made. The interpretations or opinions expressed represent the best judgment of Core Laboratories, Inc., (all errors or omissions excepted); but Core Laboratories, Inc., and its officers and employees, assume no responsibility and make no warranty or representations as to the productivity, proper operation, or profitability of any oil, gas or other mineral well or sand in connection with which such report is used or relied upon.

VERTICAL SCALE: 5" = 100'

