



# OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

November 20, 1981

Aztec Oil, Inc.  
P. O. Box 741  
Olathe, Kansas 66061

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Finley Lease, Well No. 7, located in Section 18, T-14S, R-22E, in Johnson County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on November 15, 1981.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/mkf

5 c to Olathe, Ks.

- REGISTERED ENGINEERS -

CORE ANALYSIS - WATER ANALYSIS - REPRESSURING ENGINEERING - SURVEYING & MAPPING - PROPERTY EVALUATION & OPERATION

OILFIELD RESEARCH LABORATORIES

LOG

Name Aztec Oil, Inc. Lease Finley Well No. 7

Depth Interval,  
Feet

Description

BARTLESVILLE SAND

821.0 - 821.8

Black slightly carbonaceous sandstone.

821.8 - 823.7

Brown sandstone with shale partings.

823.7 - 824.3

Gray shale.

**Oilfield Research Laboratories**

**RESULTS OF SATURATION & PERMEABILITY TESTS**

**TABLE 1**

Company Aztec Oil, Inc. Lease Finley Well No. 7

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
			BARTLESVILLE SAND				
1	831.5	22.4	52	14	66	904	415.
2	832.5	21.5	38	31	69	634	52.
3	823.4	20.1	39	55	94	608	22.