



EVANS
ENERGY
DEVELOPMENT
INC.

11 Lewis Drive

Paola, KS 66071

Oil & Gas Well Drilling
Water Wells
Geo-Loop Installation

Phone: 913-557-9083

Fax: 913-557-9084

WELL LOG

Kansas Resource Exploration & Development, LLC
 Knabe M #KRI-8
 API # 15-091-23,749
 January 16 - January 17, 2012

| <u>Thickness of Strata</u> | <u>Formation</u> | <u>Total</u> |
|----------------------------|------------------|--------------|
| 5 | soil & clay | 5 |
| 16 | lime | 21 |
| 8 | shale | 29 |
| 9 | lime | 38 |
| 7 | shale | 45 |
| 17 | lime | 62 |
| 23 | shale | 85 |
| 10 | lime | 95 |
| 2 | shale | 97 |
| 54 | lime | 151 |
| 42 | shale | 193 |
| 8 | lime | 201 |
| 16 | shale | 217 |
| 20 | lime | 237 |
| 44 | shale | 281 |
| 55 | lime | 336 |
| 4 | shale | 340 |
| 5 | lime | 345 |
| 7 | shale | 352 |
| 16 | lime | 368 |
| 168 | shale | 536 |
| 4 | lime | 540 |
| 33 | shale | 573 |
| 5 | lime | 578 |
| 127 | shale | 705 |
| 4 | oil sand | 709 |
| 2 | broken sand | 711 |
| 4 | silty shale | 715 |
| 110 | shale | 825 |
| 6 | broken sand | 831 |
| 4 | oil sand | 835 |
| 5 | silty shale | 840 |
| 60 | shale | 900 TD |

Drilled a 9 7/8" hole to 22.2'
 Drilled a 5 5/8" hole to 900'.

Set 22.2' of 7" surface casing cemented with 6 sacks of cement.

Set 888' of 2 7/8" threaded and coupled 8 round upset tubing including 3 centralizers, 1 float shoe, and 1 clamp.