

Company Paw-Cat Associates

Farm McCann

Well No2-A

Sec. 14 T. 14 R. 22 E

Loc. 160' FEL - 160' FSL, S W

County JOHNSON

Total Depth 850.30'

Comm.

Comp.

Shot or Treated

Contractor Kent Drilling Company

Issued

Casing

20 in.

10 in

15 1/2

8 1/4

- 29'


12 1/2

6 5/8

- 823'

13 3/8

5 3/16



SE SESW
- KCC

Elevation

Production D & A

Figures Indicate Bottom of Formation

Soil & Clay	10
Lime shells	18
Shale	22
Lime	39
Shale	46
Lime	55
Shale	63
Lime	77
Shale	99
Lime	173
Shale	200
Lime	208
Shale	230
Lime	236
Shale	239
Lime	248
Shale	280
Lime	282
Shale	292
Lime	319
Shale	327
Lime	347
Shale	351
Lime	354
Shale	359
Lime	366
Shale	548
Lime	550
Shale	572
Lime	577
Shale	585
Lime	597
Shale	621
Lime	623
Shale	698
Sandy shale	705
Lime	707
Shale	731
Lime	734
Shale	745
Lime	746
Shale	823

Black shale	826
Sand & Lime	829
White sand	831.50
Sand	835.60
White Sand	840.20
Black Oil Sand	845
Shale	850.30 T.D.

8" Set at 29' S.L.M. @ 806.50, & @ 831.50. 6 1/4" Set @ 823' the sandy lime showed a little oil but bled very little over the week end. The white sand showed no oil what-so-ever, but the black sand bled well but not enough to be commercial. In this well we got a show of squirrel between 698 to 705 but no bleeding.

We plugged the well as follows. 10' of soil from 850' to 840' then 5 sax cement, then pulled 6 1/4" up 700' put bridge @ 711 and 5 sax cement, then finished pulling 6 1/4" put bridge @ 173' with 6 sax cement, put bridge @ 30' with 4 sax cement, was able to retrieve only 12' of 8 1/4".