

17-14-22E

WE SERVE

The

Eastern Kansas Oil Field

STEEL PIPE AND CASING
New and Used

PUMPING UNITS

SUCKER RODS

PUMPING EQUIPMENT

VALVES AND FITTINGS

WIRE ROPE

ENGINE - ELECTRIC MOTORS
AND CONTROLS

PUMPS AND WATER SYSTEMS

V BELTS AND HOSE

POLES
HARDWARE AND WIRE

PLASTIC PIPE & FITTINGS

Kenneth R.

Johnson, Inc.

Oil-Gas-Water-Industrial Supplies

CHANUTE
(316) 431-0479

OSAWATOMIE
(913) 755-4182

BARNETT
(913) 448-5915

Nite (913) 294-3221

Nite (913) 755-3950

Log Book

Well No. 17-14-22E

Farm Kramer

(Section) 17

(Range) 14

For Ken Belisle

(Well Owner)

Kenneth R.

Johnson, Inc.

Oil-Gas-Water-Industrial Supplies

CHANUTE
(316) 431-0479

OSAWATOMIE
(913) 755-4182

BARNETT
(913) 448-5915

Nite (913) 294-3221

Nite (913) 755-3950

A. G. GLAZE DRILLING OLATHE, KS.

Thickness of Strata	Formation	Total Depth
3	Surface	3
7	Clay + Sand	10
10	Sand	20
2	Shale	22
9	Lime	31
10	Sandstone ^{grey}	41
20	Lime	61
3	Shale Dark	64
9	Lime	73
10	Shale	83
17	Lime	100
18	Shale Sandy	118
71	Lime	193
27	Shale	220
10	Lime	230
15	Shale	245
9	Lime	254
6	Shale	260
15	Lime	275
25	Shale	300
2	Lime	302
8	Shale	310
8	Lime	318
1	Shale	319
17	Lime	336
2	Shale	338

340' string

} White rset

Thickness of Strata	Formation	Total Depth	Remarks
1	BLK. SLT.	339	744 STRIAL
2	Shale	341	SEE
24	Lime	365	Bethany Falls
1	Shale	366	
4	BLK SLATE	370	338 STRIAL
2	Lime	372	
3	Shale	375	
1	Lime	376	
1	Shale	377	STRIAL 580
8	Lime	385	SLIM HEARTY
113	SANDY	498	
3	Sand Stone	506	String 600'
14	Shale	520	
10	Shale	530	
8	Lime	538	
7	SHALE SLATE	545	
2	Shale	547	
6	Lime	553	
15	Shale	600	
2	Lime	602	
4	SANDSTONE	606	CAS BUBBLES
4	BLK SLT	606	

806

RECEIVED 85
STATE CORPORATION COMMISSION

MAR 19 1982

CONSERVATION DIVISION
Wichita, Kansas

Thickness of Strata	Formation	Total Depth	Remarks
5	SEALY LIME	611	
16	Shale sandy	621	string
3	Shale	624	
5	Red Bed	629	
31	Shale	660	SLM 700
9	Sandstone	669	upper squirrel
41	Shale sandy	715	
10	Dark shale	725	
15	SANDSTONE	740	LIGHT STAIN OF LIL
5	Sandy shale	745	
5	Dark shale	750	
3	BR SHALE	753	
5	Shale	758	
3	Lime	761	
22	Shale Dark	783	
15	BLK SLT	798	
38	Shale sandy	836	
4	Black SLT	840	
21	Shale sandy	861	
1	Limp	862	Cap -
10	Sand	873	
8	Shale sandy	881	
4	Black SLT	885	
5	Shale	890	TD

