

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey
WICHITA, BRANCHAPI No. 15 — 091 — 20493
County Number

Operator

borne-joss

Address

15451 Antioch Stanley Kansas 66223

Well No.

11

Lease Name

Meyer

Footage Location

820

feet from (N) line

165

4465 FSL & 2475 FEL-KCC

feet from (W) line

Revised

Principal Contractor

A.G. Glaze Drilling Co.

Geologist

Spud Date

12/6/81

Date Completed

12/7/81

Total Depth

882 ft.

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

McClaskey Vacuum Transport


S 23 T 14 R 22 E

Loc. NW 1/4 of NE 1/4

SW NW NE-KCC

County Johnson

RECORDED

640 Acres
N

Locate well correctly

Elev.: Gr. _____

DF. _____ KB. _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 1/4"	8"	28.55	25'	Portland	5	
Production	6 1/4"	2 7/8"	7.66	850'	Portland	146	Premium Gel 2.5%

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	1 11/16 glas-jet	829 - 839 ft
TUBING RECORD					
1"	Setting depth 850 ft	Packer set at none			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
fracturing: 25 sack 12 X 30 sand, 15 sack 10 X 20 sand, 50 lb	829 - 839 ft
rock salt, 50 lb water gel.	

INITIAL PRODUCTION

Date of first production 12/20/81		Producing method (flowing, pumping, gas lift, etc.) pumping			
DATE OF PRODUCTION PER 24 HOURS	Oil 5	Gas 0	Water 1/2	Gas-oil ratio 0	CFPB
Disposition of gas (vented, used on lease or sold) vented			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Driller's Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Driller's Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

