

Company Hughes Bros.

23-14-222
Sec. 23 T. 14 R. 22

Farm Eldon Gordon

No. 1

Loc. SE 1/4

County Johnson

Total Depth 875.7


Comm.

Comp. Not known, but between 1960 and 1966

Shot or Treated

Contractor

Issued



Casing

20 in.	10 in
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation

Production

Figures Indicate Bottom of Formation

Soil	6	6		Sand	3.2	859.7
Clay	31	37	yellow	Shale	3	862.7 sdy
Lime	22	59		Shale	6.3	869 sdy.
Shale	7	66		Shale	6.7	875.7 TD
Lime	9	75			TD=875.7	
Shale	8	83				
Lime	20	103				
Shale	9	112				
Lime	86	198	At 175' 5' water sd.			
Shale	17	215	blue			
Lime	9	224				
Shale	18	242	blue			
Lime	20	262				
Shale	34	296	blue			
Lime	3	299				
Shale	9	308	blue			
Lime	27	335	water @325' 1/2 @hr.			
Shale	6	341	drk.			
Lime	23	364				
Shale	5	369				
Lime	3	372				
Shale	9	381	Top of Hertha ^{Hertha} slm.			
Lime	10	391	bottom of Hertha ^{Hertha} F Hertha			
Shale	175	566				
Lime	4	570				
Shale	4	574				
Lime	1	575				
Sand	5	580	Gas Slm 580'			
Sand	5	585	Some shale			
Shale	5	590	sd.			
Shale	7	597				
Lime	4	601				
Shale	3	604	sd.			
Shale	6	610	Limey			
Lime	2	612	Scott			
Shale	11	623				
Red Rock	5	628				
Shale	20	648	Drk. Then ^{lite}			
Lime	2	650				
Lime Shells	25	675				
Shale	175	850	Slm 848			
Lime	2.5	852.5	Oil sh.			
Sand	4	856.5				

Producing well 7/20/64