

Howard P. Thach  
 Company ~~Kent Drilling Co.~~

Sec. 23 T. 14 R. 22E  
 Loc. 100' FEL--165' FNL of W 60A N  
 County JOHNSON

Farm McCann Well No. 1-C


Total Depth 839.50'

Comm. \_\_\_\_\_ Comp. \_\_\_\_\_

Shot or Treated \_\_\_\_\_  
 Contractor **Kent Drilling Co.**

Issued \_\_\_\_\_  
 Casing

20 in.	10 in	@ 6'
15 1/2	8 1/4	44
12 1/2	6 5/8	817
13 3/8	5 3/16	
	4"	- 839 1/2'



Elevation

Production

Figures Indicate Bottom of Formation

Soil & Clay	6	Set 10" @ 6'
Sand Stone	17	8" @ 43.95
Lime	31	6 1/4 @ 817
Shale	37	4" @ 839.50
Lime	46	
Shale	55	
Lime	70	
Shale	91	
Lime	165	
Shale	192	
Lime	200	
Shale	220	
Lime	226	
Shale	229	
Lime	238	
Shale	271	
Lime	273	
Shale	282	
Lime	308	
Shale	316	
Lime	338	
Shale	342	
Lime	345	
Shale	349	
Lime	358	
Shale	530	
Lime	533	
Shale	560	
Lime	564	
Shale	578	
Lime Shells	590	
Red Bed	592	
Shale	730	
Lime Shells	734	
Shale	773	
Lime Shells	776	
Shale	812	
Lime	813	
Shale Grey	816	
Shale Blk.	819.50	
Oil Sand & Sh.	839.50 T.D.	

S.L.M. @ 801.65, @ 820.30, @ 839.50.  
 This well had a very good dark sand from 819.50 to 823.50 for 4 Ft. of good bleeding sand. Then from 823.50 to 824.00 for .50 of limey sand, then sandy shale to 830.00 for 7' of this, then white sand to 831.50. then 8 ft. of shale to T.D. This well was perforated from 820 to 824 with nine shots, then fracked with 10,000 lbs. of sand & 200 lbs. of oil.