

all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

☐ Other (explain).....
(purchased from city, R.W.D. #)

SIDE TWO

Operator Name ... Brown Bear Energy, Inc. ... Lease Name ... Gordon ... Well #. 3.A.

Sec... 30 ... Twp... 14 ... Rge... 22 ... ☒ East ☐ West County... Johnson ...

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☐ Yes ☒ No
 Samples Sent to Geological Survey ☐ Yes ☒ No
 Cores Taken ☐ Yes ☒ No

Formation Description
☐ Log ☒ Sample

Name Top Bottom

0-8 Soil & Clay
 8-26 Snady Lime
 26-85 Shale
 85-131 Lime w/Shale breaks
 131-224 Shale w/Lime breks
 224-291 Lime w/Shale breks
 291-358 Shale w/Lime breks
 358-431 Lime w/ Shale breaks
 431-619 Shale/Pleasanton
 619-661 Lime w/Shale breaks
 661-781 Red sandy shale
 781-785 Black coal
 785-787 Lime
 787-881 Dark Shale
 881-882 Cap rock
 882-888 Sand with oil show

888-892 Laminated Sand
 892-935 Shale TD

CASING RECORD ☐ New ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface Casing	6 5/8	6 5/8		21	Portland	6	
Production Casing	2 7/8			924	Portland	100	

PERFORATION RECORD

Shots Per Foot	Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
	not completed yet	not completed yet	
3	888-892	250 GAL OF ACID	

TUBING RECORD Size Set At Packer at Liner Run ☐ Yes ☒ No
 2 7/8

Date of First Production Producing Method
☐ Flowing ☐ Pumping ☐ Gas Lift ☐ Other (explain).....