

Noted by J. Miller

10-14-25E

Company Dr. Francis

Sec. 10 T. 14S
Loc. SW 1/4 SE 1/4 NE 1/4

R. 25E

Farm Fry

No. -878-

Total Depth 419

County Johnson


Comm. 8-19-36

Comp. 8-28-36

Shot or Treated

Contractor Hay Bradford

Issued



Casing

20 in.	10 in.	
15 1-2	8 1-4	Drive Pipe 34'
12 1-2	6 5-8	375'
13 3-8	5 3-16	

Elevation R ± 874 F. G.

Production D & M

Figures Indicate Bottom of Formation

Surface	7'	Lite gray shale	351
Yellow clay	20	Red bed & green shale	360
River mud & gravel	34	Dark shale	375
Water - set 34' of 8" drive pipe		Lime	378
Lime	49	Black shale	382
Shale	51	Gray shale - dark	386
Lime	60	Lite gray shale	392
Shale	61	Black slate	405
Lime	63	Sand	412
Shale	64	Lite sandy shale	419
Lime	65		
Black slate	69 ✓		
Shale	73		
Lime B F	90		
Very lt. water in lower part of BF			
Dark shale	95		
Lime	97		
Shale	101		
Lime - case dardened	111		
/gray shale	157		
Lime	159		
Sandy gray shale	205		
very muddy at the base			
Muddy dark gray shale	226		
Sand	231 ✓		
Sandy shale lite	241		
Pale muddy green shale	261		
Shale gray to brown	275		
Dark shale	283		
Gray shale muddy	305		
Lite sandy shale	312 ✓		
Dark shale muddy	320		
Lime hard Lex. cap.	324		
Black slate - show of			
HFW salty gas	333		
Lime	336		
Shale	337		
Lime - very hard	346		