

6-15-1E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company-DONALD T. INGLING ET AL
Farm- Riordan No. 1

SEC. 6 T. 15 R. 1E
SE SE SW

Total Depth. 2602
Comm. 12-29-54 Comp. 1-9-55
Shot or Treated.
Contractor. Donald T. Ingling
Issued. 3-12-55

County Dickinson
KANSAS



CASING:

8 5/8" 100' cem. w/60 sx
4 1/2" 2590' cem. w/40 sx

Elevation. 1319 DE

Production. 54 bbls. oil

Figures indicate Bottom of Formations.

clay & shale	40
shale & shells	100
lime	580
lime & sdy shale	720
lime & shale	800
shale & shells	1495
lime	1835
shale	1903
lime	2315
shale	2370
shale & lime	2420
shale	2581
sand	2588
Mississippi	2602
Total depth	

Scout Tops:	
Lansing	1946
Burgess sand	2583
Mississippi	2588