

11-15-1E

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company. F.W. VISHNEFSKE
Farm. Robson No. 1

SEC. 11 T. 15 R. 1E
NW NE NW

Total Depth. 2417'
Comm. 11-5-57 Comp. 11-11-57
Shot or Treated.
Contractor. Greenland Drlg. Co.
Issued. 12-28-57

County Dickinson

KANSAS



Elevation. 1217 RB

Production. Dry

Figures indicate Bottom of Formations.

CASING:	
8 5/8" 140'	
5 1/2" 2410'	
shale-clay	90
lime-shale	140
lime-shale w/red bed	
stks	230
shale-lime	1555
lime	1605
shale-lime	1756
brn lime-shale	1760
shale-lime	2409
Mississippi	2415 RTD
Mississippi	2417
Total Depth	

2415
1217
1298

TOPS:
Lansing 1790
Weathered Mississippi 2410
Mississippi 2415

Top of Mississippian was encountered @ 2409 w/good oil show and good odor. Drilled in 9', still oil and better porosity. Casing was set @ 2409 w/Cmtrl. Float show which did not hole, and hole filled up. After drilling out cement and swabbing, we got quantity of extremely heavy oil and wtr broke in at bottom. Well was abandoned because of heavy oil and wtr. problem.