

Best Scanned Copy

REX & MORRIS DRILLING COMPANY

EL DORADO, KANSAS

January 29, 1960

Rex & Morris Drilling Company
Cooperative Refinery Association

Re: Moore #1, NW SW NW
Section 1-15S-7E
Morris County, Kansas

Dear Sirs:

This report on the subject well is based on microscopic examination of rotary cuttings from 1100 feet to the total depth of 2530 feet. All measurements were taken from the rotary drive bushing, which was 3 feet above derrick floor and 5 feet above ground level.

The following tops were picked:

Elevation (R.B.)	(+1381)
Heebner Shale	1126 (+ 255)
Toronto Limestone	1178 (+ 203)
Douglas Shale	1212 (+ 169)
Douglas Sand	1314 (+ 67)
Lansing-Kansas City	1402 (- 21)
Base Kansas City	1728 (- 347)
Conglomerate	1952 (- 571)
Kinderhook Shale	1982 (- 601)
Hunton Dolomite	2063 (- 682)
Maquoketa Shale	2226 (- 845)
Viola Dolomite	2314 (- 933)
Simpson Dolomite	2419 (-1038)
Arbuckle Dolomite	2505 (-1124)
R. T. D. and Total Depth	2530 (-1149)

Due to absence of any oil shows and to extremely low datum on lower horizons, this test is declared dry and abandoned.

Yours very truly,

Paul D. Koontz

Paul D. Koontz,
Geologist

PDK:ead