


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRIG. CO., INC.
 Farm- Jones No. 1

SEC. 16 T. 15 R. 11E
 SE SE NE

Total Depth. 3260'
 Comm. 8-12-56 Comp. 9-7-56
 Shot or Treated.
 Contractor. White & Ellis Drlg. Inc.
 Issued. 10-6-56

County Wabaunsee
 KANSAS



Elevation. 1387' KB

CASING:

8 5/8" 130' w/90 sx cem.
 5 1/2" 3254' w/75 sx cem.

Production. Dry

Figures indicate Bottom of Formations.

soil 2
 clay 8
 lime 18
 shale 32
 lime 65
 shale 68
 lime 85
 shale 88
 lime 95
 shale 100
 lime 112
 shale 115
 lime 118
 wtr sand 122
 shale 125
 lime 127
 shale-shells 1430
 lime 1450
 shale-shells 1480
 lime 1530
 shale-shells 1917
 lime 1998
 shale-shells 2084
 lime 2112
 shale-lime strks 2118
 lime 2128
 lime-shale strks 2150
 lime 2196
 shale-lime strks 2315
 shale-shells 2390
 lime 2438
 shale lime strks 2464
 lime 2500
 lime shale strks 2572
 shale-shells 2592
 lime-shale strks 2796
 shale-shells 2808
 shale lime strks 2892
 lime strks 2950
 grady shale-lime strks 2970
 lime shale strks 2040
 shale 2096
 shale-shells 2140
 lime 2160
 shale-shells 2421
 Burgess Section 2444
 shale 2458
 Mississippi chert 2472
 lime 2581
 chatty rgh strks 2589
 lime 2862
 shale-shells 2904
 shale 2976
 lime 2998
 Dolomite 3007
 lime 3023
 shale lime strks 3105
 lime 3166
 brwn dolomite-shale strks 3182
 " " " (SO)3190

Dolomite	3210	
shale-shells	3203	
Simpson dolomite	3234	
sand	3254	
lime	3260	
Total Depth		
TOPS:		
Kansas City	Sample 1592	Schl 1581
B /Kansas City	1790	1792
Mississippi Lime	2472	2464
Kinderhook shale	2819	2814
Weisner ? sand	2957	
Hunton	2976	2952
Maquoketa shale	3015	3016
Viola	3106	3094
Decorah	3177	3173
Simpson Dolomite	3182	3176
Simpson sand	3200	3194
Arbuckle	3246	3240

DST #1 - 3182-3190. Open 1 hr. Weak blow for 32 min. then died. Rec. 10' oil & 55' watery & slightly OCM. BHP 825#, IFP 75#, FFP 75#.

DST #2- 3202-3208'. Open 1 hr. Strong blow throughout test. Rec. 900' sulphur water. BHP 1080#, IFP 90#, FFP 435#.