

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

7-15-12E


COMPANY **HIGH PLAINS PRODUCTION**

SEC. 7 T.15 R. 12E  
 LOC. NE NE SW

FARM **Waugh** NO. **1**

COUNTY **Wabaunsee**

TOTAL DEPTH **3060'**  
 COMM. **1-31-68** COMP. **2-8-68**  
 SHOT OR TREATED  
 CONTRACTOR **Donelson Drilling**  
 ISSUED **9-7-68**



CASING

20	10	
15	8	5/8" 314' cem w/ 225 sx
12	6	
13	5 1/2"	3056' cem w/ 125 sx

ELEVATION **1361' KB**

PRODUCTION **168 BOPD, NW**  
**SIMP 3056-60 GRAV 30**

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Hole	320'
Shale & Lime	1485'
Lime	1712'
Shale & Lime	2351'
Lime (Miss.)	2408'
Lime & Chert	2560'
Lime	2690'
Shale & Lime	2928'
Lime	3035'
Shale	3037'
Dolomite - Sand	3048'
Shale & Sand	3060' TD

**RECEIVED**  
 STATE CORPORATION COMMISSION  
**FEB 15 1968**  
 CONSERVATION DIVISION  
 Wichita, Kan.

<b>TOPS: SMP</b>	
Mississippi	2351
Kinderhook	2691
Misner	2829
Hunton	2833
Viola	2932
Simpson shale	3034
Simpson Dolomite	3037
Simpson sand	3057
RTD	3060