

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

*plot on Sample  
strip*


GULF OIL CORPORATION.  
C.C. Peterson No. 1.

SEC. 20 T. 15 R. 16 E.  
SW SE SW

586

Total Depth. 2217  
Comm. 5-28-42 Comp. 6-18-42  
Shot or Treated.  
Contractor.  
Issued. 11-14-42

County Osage



CASING.

85/8" 94' Left in cemented.

Elevation. 1027.15

Production. DRY.

Figures Indicate Bottom of Formations.

lime stone and shale	61'
lime and shale	99
shale and lime shell	350
shale and shells	477
lime	520
shale and broken lime	560
shale	640
lime	668
lime and shale	808
lime	846
shale and shells	960
lime and shale	1347
sdv shale	1531
lime	1546
lime and chert	1706
lime	1832
shale and lime	1861
shale	1903
shale and lime	1910
shale and lime	1940
lime	1963
lime and chert	1982
lime	2079
Arbuckle lime	2217

Total Depth.

Base Oroad	180
Top Lansing	460
Top Kansas City	635
Base Kansas City	845
Top Mississippian	1531
Base Mississippi	1831
Top Misoner	1908
Top Hunton	1928
Top Viola	1972
Top Simpson	2047
Top Arbuckle	2079

Plugged 6-18-42