

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company. SCHERMERHORN OIL CORPORATION
 Farm. Johanning No. 1

SEC. 17 T. 15 R. 19E
 SW SW NW NE

Total Depth. 1902
 Comm. 2-22-56
 Shot or Treated.
 Contractor.
 Issued. 4-21-56

Comp. 3-23-56

County Douglas
 KANSAS



CASING:

8 in. @ 12.2'

Elevation. 1059 DF

Production. Dry

Figures indicate Bottom of Formations.

soil	2	shale	901	Mississippi chert	1427
black shale	8	lime	908	Mississippi lime	1533
lime	12	shale	918	limey sandy shale	1548
shale	110	lime	920	brown lime	1552
sandy shale	131	limey shale	936	limey sandy shale	1572
fresh water sand	149	limey sandy shale	964	lime	1642
lime	152	shale	977	shale	1649
shale	191	limey sandy shale	981	shale & lime	1652
lime	199	sandy shale	996	shale	1677
shale	267	limey shale	1010	lime	1806
lime	270	shale	1020	brown dolomite	1825
sand	284	limey	1021	sand	1857
lime	299	shale	1027	limey sand	1869
black shale	307	limey	1029	Arbuckle lime	1902
lime	315	shale	1035	Total Depth	
shale	319	limey	1040		
lime	351	sandy shale	1056	TOPS: SAMPLE SCHLUM.	
sandy shale	364	limey	1063	Lansing 267 270	
limey shale	401	sandy shale	1067	Kansas City 465 470	
hard sand	410	limey shale	1080	Base K. C. 656 660	
limey shale	421	sandy shale	1085	Marmaton 812 810	
sand	455	limey shale	1089	Cherokee 920 910	
limey sandy shale	460	sandy shale	1099	Miss. lime 1402 1402	
shale	465	shale	1102	Base. Miss. 1642 1642	
lime	501	coal	1104	Viola 1677 1678	
shale	514	shale	1108	Simpson sand 1825 1822	
lime	527	sandy shale	1114	Arbuckle 1878 1856	
shale	536	purplish, red &			
red bed	540	green shale	1121		
shale	556	shale	1125	DST #1: 1679-84, open 45	
lime	566	hard sand	1128	min. SI 20 min. sl. bl.	
shale	568	sand	1137	8 min. rec. 40' mud, no	
lime	561	sandy shale	1140	show oil or gas. IFP 15#,	
shale	583	shale	1164	FFP 25#, BHP 180#	
lime	609	sand	1167		
black shale	616	sandy shale	1199		
lime	640	limey shale	1206		
black shale	644	sandy shale	1223		
lime	656	limey	1224		
shale	680	sandy shale	1244		
sandy shale	722	limey	1246		
lime	723	sandy shale	1263		
sandy shale	735	limey shale	1276		
shale	772	sandy shale	1284		
lime	790	limey shale	1289		
limey shale	810	shale	1298		
shale	811	limey shale	1309		
limey shale	827	redish lime	1314		
lime	840	shale	1322		
shale	846	lime	1323		
lime	850	shale	1336		
sandy shale	857	coal	1338		
lime	859	shale	1379		
shale	868	limey shale	1382		
lime	876	sand	1389		
shale	885	coal	1393		
lime	890	hard shaley sand	1401		