



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

April 8, 1981

Kent Fry
P. O. Box 3747
Lawrence, Kansas 66044

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Pearson Lease, Well No. 3-81, located in Section 12, T-15S, R-20E, in Douglas County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and was submitted to our laboratory on April 1, 1981.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/kas

5 c to Lawrence, Kansas

OILFIELD RESEARCH LABORATORIES

LOG

Name Kent Fry Lease Pearson Well No. 3-81

Depth Interval, Description

Feet

SQUIRREL SAND

844.0 - 846.3	Brown and gray laminated sandstone and shale.
846.3 - 851.3	Brown sandstone.
851.3 - 852.2	Brown and gray laminated sandstone and shale.
852.2 - 852.7	Brown sandstone.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Kent Fry Lease Pearson Well No. 3-81

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	844.6	18.3	47	35	85	667	3.7
2	845.5	18.5	48	36	84	689	5.6
3	846.7	23.4	31	32	63	563	47.
4	847.6	23.4	32	31	63	581	99.
5	848.6	22.1	49	28	77	840	62.
6	849.6	20.1	65	22	87	1014	52.
7	850.5	23.1	66	17	83	1183	47.
8	851.5	22.8	57	21	78	1008	5.4
9	852.5	21.1	31	20	51	508	62.