

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG

4450 FSL and 5225 FEL


NW

KCC Record

API No. 15 — 045 — 20,201
County NumberS. 12 T. 15 R. 20 E X
W

Loc. NW 1/4

County Douglas

640 Acres
N

Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

Operator

Kent Fry

Address

P. O. Box 3747, Lawrence, KS 66044

Well No.

7-81

Lease Name

Pearson

Footage Location

770

feet from (N) (S) line

75

feet from (E) (W) line

Principal Contractor

C. & R. Drilling

Geologist

Spud Date

Date Completed

4/81

Total Depth

890

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

Maclaskey

CASING RECORD

Report of oil strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 1/4	6 1/4		103	Portland	110	Premium Gel 3 sacks
Production	5 1/4	2 3/8	3.75	887			

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	1 11/16 glass jets	842-852
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fracture - 50 sacks sand, 100 barrels water	842-852

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
5/7/81		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	1-2 bbls.	MCF	1-2 bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Vented			842-852		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No.	Lease Name	
S _____ T _____ R _____ E _____ W _____		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received	Signature Title Date
---------------	---

WELL RECORD

12-15-20E

P1

Well No. 7-81 Farm Pearson Producer Advanco

Location _____ Sec. 12 Twp. 15 Rg. 20E

Elevation _____ State Kansas County Douglas

Kind (Oil, Gas, Water, Dry Hole) Oil Contractor G & R Drilling

Producing formation Squirrel Top _____ Bottom _____

Shot with _____ qts. _____ from _____ to _____

Packer Set at _____ Kind _____ Size _____

Liner _____ from _____ to _____ Perforated from _____ to _____

LOG

Thick-ness	Strata	Depth	Thick-ness	Strata	Depth
	Soil & Clay	7	8	Lime	742
76	Sand	83	5	Shale	747
114	Shale	197	6	Lime	753
5	Lime	202	8	Shale	761
6	Shale	208	11	Lime	772
15	Lime	223	11	Shale	783
8	Shale	231	4	Lime	787
8	Lime	239	15	Shale	802
5	Shale	244	6	Lime	808
20	Lime	264	33	Shale	841
28	Shale	292	12	Sand-Oil	853
19	Lime	311	3	Sandy Shale	856
74	Shale	385	34	Shale	890
7	Lime	408			
18	Shale	426			
7	Lime	433			
23	Shale	456			
17	Lime	473			
10	Shale	492			
25	Lime	517			
7	Shale	524			
24	Lime	548			
3	Shale	551			
5	Lime	556			
3	Shale	559			
7	Lime	566			
168	Shale	734			

Total Depth 890'

Open Hole

Surface

Casing 103' at

Casing at

Casing at

Cement

2"

Tubing 887'

Rods

Additional Information

1-Seating Nipple

1-Float Shoe

1-2" Clamp

Completed

O. K.

Superintendent