


KANSAS

2714 FSL and 3594 FEL
SW SE NW-KCC RecordWELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey
WICHITA, BRANCHAPI No. 15 — 045 — 20,093
County NumberS. 1 T. 15 R. 20 E
Loc. 990' FEL & 60' FSL NW

County Douglas

640 Acres
N

Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

Operator M & W Oil			
Address c/o Bogle, RR 1, Wellsville, KS 66092			
Well No. # J2	Lease Name Johnson SW SE NW-KCC Record		
Footage Location 60 feet from (N) (S) line		990 feet from (E) (W) line	
Principal Contractor Michael Drilling		Geologist none	
Spud Date 8/12/79	Date Completed 8/15/79	Total Depth 928	P.B.T.D.
Directional Deviation		Oil and/or Gas Purchaser Town Oil - LaJet, Inc	

CASING RECORD

Report of oil strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	8-1/8	6-1/4	17#	25	Neet	1	
production	5-1/4	2-3/8	3.75	830	Portland A	110	2 % gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at
2-3/8	830	830

TUBING RECORD

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
10 sx 12-30 sand	830-840
30 sx 10-20 sand	
25 # water gel	

INITIAL PRODUCTION

Date of first production 1/21/80		Producing method (flowing, pumping, gas lift, etc.) pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 2 bbls.	Gos 0 MCF	Water 0 bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold) na			Producing interval(s) 830-840		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

Lease Name

S ____ T ____ R ____ E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

See attached sheet

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Title

Date

PI
Farm - Johnson

Contractor - Michael Drilling

1-15-20e

County - Douglas

Well - J-2

Lease Owner - M & W

Permanent Casing

<u>Size</u>	<u>Amount</u>	<u>Condition</u>	<u>Cement</u>
<u>Strata</u>	<u>Total Depth</u>	<u>Strata</u>	<u>Total Depth</u>
Soil & Clay	24	Slate	760
Lime	26	Lime	777
Shale	169	Shale	790
Lime	173	Lime	792
Shale	181	Shale	800
Lime	194	Lime	806
Shale	202	Shale	816
Lime	209	Shale & Sand	829
Shale & Shells	216	Sand Oil	857
Lime	241	Shale	911
Shale & Shells	252	Lime	915
Lime	255	Shale	928 T. D.
Shale	264		
Lime	283		
Shale	356		
Lime	379		
Shale	397		
Lime	404		
Shale	429		
Lime	446		
Shale	451		
Lime	452		
Shale	463		
Lime	490		
Shale & Shells	495		
Lime Shells	518		
Shale	523		
Lime	537		
Shale & Shells	681		
Lime	684		
Shale	690		
Lime	696		
Shale	706		
Lime	713		
Shale	717		
Lime	723		
Shale	731		
Lime	740		
Shale	753		
Lime & Shells	756		