

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 045 — 20,092
County NumberState Geological Survey
WICHITA, BRANCH

S. 1 T. 15 R. 20 E

Loc. 1320' FEL & 60' FSL NW

County Douglas

2700 FSL & 3960 F

Operator

M & W Oil

Address

c/c Bogle, RR 1, Wellsville, KS 66092

Well No.

#J1

Lease Name

Johnson

Footage Location

60 2700 FSL & 3960 FEL 1320
feet from (N) (S) line feet from (E) (W) line

Principal Contractor

Michael Drilling

Geologist

none

Spud Date

8/11/79

Date Completed

8/14/79

Total Depth

928'

P.B.T.D.


Directional Deviation

Oil and/or Gas Purchaser

Town Oil - LaJet, Inc.

640 Acres

N



Locate well correctly

Elev.: Gr.

DF

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	8-1/8	6-1/4	17#	25	Neet	1	
production	5-1/4	2-3/8	3.75	828	Portland A	110	2% gel

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8	828	828

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
10 sx 12-30 sand	828-845
30 sx 10-20 sand	
25# water gel	

INITIAL PRODUCTION

Date of first production 1/21/80	Producing method (flowing, pumping, gas lift, etc.) pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 2 bbls. Gas 0 MCF Water 0 bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) na	Producing interval (s) 828-845

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

Lease Name

S____T____R____E____
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

See attached sheet

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Title

Date

Farm - Johnson *P1*

Contractor - Michael Drilling

County - Douglas

1-15-20E

Well - J-1

Lease Owner - M & W

Permanent Casing

<u>Size</u>	<u>Amount</u>	<u>Condition</u>	<u>Cement</u>
<u>Strata</u>	<u>Total Depth</u>		
Soil & Clay	19	Lime	768
Lime	21	Shale	770
Shale	161	Lime Shells	788
Lime	166	Lime	794
Shale	170	Shale	814
Lime	188	Sand oil	817
Shale	196	Shale	818
Lime	203	Sand oil	850
Shale	208	Shale	928
Lime	237		
Shale	257		
Lime	276		
Shale	349		
Lime	373		
Shale	388		
Lime	396		
Shale	420		
Lime	438		
Shale	443		
Lime	445		
Shale	455		
Lime	482		
Shale	488		
Lime	512		
Shale	515		
Lime	530		
Shale	672		
Lime	675		
Shale	681		
Lime	684		
Shale	696		
Lime	703		
Shale	709		
Lime	712		
Red Bed	714		
Shale	720		
Lime	730		
Shale	744		
Lime	748		
Slate	751		