

4-15-206 Plotted
 LM.
 Plotted
 E. m.
 NE-SW-SE-NW

Webster No. 4

NW. 1/4, Sec. 9, Twn. 15 S., Rg. 20 E.
 Completed - Oct. 28, 1937.

Depth in feet	Thickness in feet
4	Sandy loam 4
25	Shale sandy 21
60	Sandstone 35
71	Sandstone - water 11
73	Lime hard 2
194	Shale grey 113
196	Lime brown 2
198	Shale dark grey 2
199	Lime 1
210	Shale light grey 11
230	Lime hard 20
237	Shale black 7
249	Lime 12
252	Shale dark grey 3
284	Lime sandy 32
300	Shale grey sandy 16
340	Lime hard 40
387	Shale grey 47
409	Lime white 22
424	Shale grey 15
433	Lime brown 9
450	Shale grey 17
460	Lime white soft 10
466	Shale dark 6
477	Lime 11
480	Shale dark 3
482	Lime - chert 2
495	Shale dark grey 13
505	Lime sandy 10
520	Lime white hard 15
525	Shale dark grey 5
552	Lime hard 27
563	Shale dark 11
567	Lime brown 4
579	Shale dark 12
582	Lime hard 3
605	Shale light 23
610	Shale dark - gas 5
625	Sandstone - salty water 15
733	Sandstone & shale 108
735	Lime 2
740	Shale black 5
742	Shale grey 2
749	Lime 7
768	Shale light grey 19
772	Lime 4
781	Shale light grey 9
790	Shale dark to black 9
792	Lime brown 2
799	Shale black - salt water 7
812	Lime & black shale 13
818	Shale maroon 6
825	Shale dark grey 7
827	Shale black 2
829	Lime brown 2

Depth	Thickness
834 ...	Shale white ... 5
852 ...	Sandstone - oil .18
856 ...	Shale blue 4
858 ..	bottom of hole.
	##

----set 790 ft. of 6 1/4 casing

----- set 4 and 7/8 casing.

(Composite log of both the completed hole and a shallower well 300' away)