

KANSAS

State Geological Survey

WELL COMPLETION REPORT AND
DRILLER'S LOG

WICHITA BRANCH

S. 19 T. 15 R. 20 E

Loc. 1000 FEL 800 FSL

API No. 15 — 059 — 21897
County Number

Operator

P & W Oil

Address

5987 Miller St., Arvada, Co 80004

Well No.

BBR 3

Lease Name

Brady

Footage Location

800

feet from (S) line

1000

feet from (E) line

Principal Contractor

Wellsville Development

Geologist

none

Spud Date

4-15-81

Date Completed

4-18-81

Total Depth

825'


P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

Lajet, Inc.

County Franklin

640 Acres
N

Locate well correctly

Elev.: Gr.

DF KB

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	8 1/8	6 1/4	17#	25'	Neet	1	
production	5 1/4	2 3/8	3.75	800'	Portland A	105	2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			31	1 11/16 glasjets	765-780
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8	800'	800'			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
10 sx 12-30 sand	765-780
40 sx 10-20 sand	
75 # water gel	

INITIAL PRODUCTION

Date of first production 5-8-81		Producing method (flowing, pumping, gas lift, etc.) pumping			
RATE OF PRODUCTION PER 24 HOURS		Oil 1 bbls.	Gas 0 MCF	Water 0 bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) na			Producing interval(s) 765-780		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No.	Lease Name		
S ___ T ___ R ___ E W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME DEPTH
see attached log <!-- Empty log area -->			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Title 6/30/81 Date		

19-15-20 SEP

Farm - Brady

Contractor - Wellsville Development, Inc

County - Franklin

Drilling Started -

P/

Well - BBR-3

Drilling Completed -

Lease Owner - L&W

Permanent Casing

Size

Amount

Condition

Percent

Strata

Total Depth

Soil & Clay	3
Yellow Clay	13
Shale	20
Lime	75
Shale	77
Lime	135
Shale	138
Lime	197
Sand	210
Shale	232
Lime	242
Shale	278
Lime	298
Shale	
Lime	315
Shale	395
Lime	450
Shale	455
Lime	470
Shale	620
Lime	630
Shale	667
Lime	674
Shale	680
Lime	695
Shale	722
Lime	724
Shale	728
Lime	739
Shale	740
Sand	760
Shale	765
Oil Sand	780
Shale	785
Shale	825

470
770
790