

WELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey
WICHITA BRANCHAPI No. 15 — 059 — 21925
County Number

Operator

P & W Oil

Address

5987 Miller, Arvada, CO 80004

Well No.

BBR 4

Lease Name

Brady

Footage Location

800

feet from (44) (S) line

1330

feet from (E) (33) line

Principal Contractor

P & W Drilling

Geologist

none

Spud Date

4/21/81

Date Completed

4/24/81

Total Depth

850'

P.B.T.D.

Directional Deviation


Oil and/or Gas Purchaser

LaJet Inc.

S. 19 T. 15S R. 20 E

Loc. 800 FSL 1330 FEL

County Franklin

640 Acres
N

Locate well correctly

Elev.: Gr.

DF

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	8 1/8	6 1/4	17#	25	Neet	1	
production	5 1/4	2 3/8	3.75	825'	Portland A	105	2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			31	1 11/16 glasjets	762-786
TUBING RECORD					
Size	Setting depth	Packer set at			
5 1/4	2 3/8				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
13 sx 12-30 sand	762-786
25 sx 10-20 sand	
66 # water gel	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)			
7-9-81	pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	1 bbls.	0 MCF	0 bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	
na			762-786	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No.	Lease Name	
S ____ T ____ R ____ E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
see attached log				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature
	Title
	Date

Farm - Brady

Contractor - P & W Drilling 19-15-20e

County - Franklin

Drilling Started - 4-21-81

Well - BBR 4

Drilling Completed - 4-24-81

Lease Owner - P&W

Permanent Casing

<u>Size</u>	<u>Amount</u>	<u>Condition</u>	<u>Percent</u>
<u>Strata</u>	<u>Total Length</u>		
Soil & Clay	21		
Shale	80		
Lime	87		
Shale	92		
Lime	110		
Shale	112		
Lime	135		
Shale & Shells	185		
Sand	200		
Shale & Shells	222		
Lime	224		
Shale	230		
Lime	342		
Shale	360		
Lime	370		
Sand	380		
Shale	385		
Lime	462		
Shale	625		
Lime	642		
Shale	664		
Lime	670		
Shale & Shells	695		
Lime Shells	705		
Shale	724		
Lime	727		
Shale & Shells	730		
Lime	731		
Shale	743		
Sand oil	786		
Shale	804		
Lime	806		
Shale	850	T.D.	

743
462

281