

JOE SUTCLIFFE

Well Record

119 S. GRANT, CHANUTE KANSAS
 5706 N. BROADWAY, WICHITA, KANSAS

PHONE HK 1-1940 CHANUTE.
 PHONE TEMPLE 8-3601 WICHITA

(COMPLETE LINE OF NEW & USED PIPE - BELTING - STORAGE TANKS - WIRE LINES)

Well No. W 1 Farm Woods Producer Schwader Oil Co.
 Location Franklin County Sec. 29 Twp. 15 S. Rg. 20 E.
 Elevation _____ State Kansas County Franklin
 Kind (Oil, Gas, Water, Dry Hole) _____ Contractor Sutcliffe Pipe & Supply
 Producing formation _____ Top _____ Bottom _____
 Shot with _____ qts. _____ from _____ to _____
 Packer set at _____ Kind _____ Size _____
 Liner _____ from _____ to _____ Perforated from _____ to _____

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
	Soil	3	5	Shale	460
	Clay	10	15	Sand	475
70	Shale	80	25	Shale	500
5	Lime	85	10	Sandy shale	
				water	510
	Shale	91	2	Lime	512
	Lime	108	118	Shale	630
	D. Shale	117	13	Lime	643
5	Lime	122	15	Shale	658
4	Shale	126	4	Lime	662
21	Lime	147	17	Shale	679
27	Muddy Shale	174	8	Shale	687
20	Lime	194	5	Sand water	692
23	Shale	270	5	Lime	697
12	Lime	287	10	Shale	707
	D. Shale	305	1	Lime	708
5	Sandy Shale	310	7	Shale	715
7	Lime	317	3	Lime	718
13	Shale	330	8	Shale	726
	Red bed	335	50	Sand	776
	Shale	346			
10	Lime	356			
4	Shale	360			
4	Lime	364			
12	Shale	376			
8	Lime	384			
3	Shale	387			
	Lime	405			
9	Sandy Shale	414			
24	Lime	438			
4	Slate	442			
13	Lime	455			

Total Depth 776'
 Open Hole
 Casing 8" at 0 to 426
 Casing _____ at _____
 Casing _____ at _____
 Cement _____
 Tubing _____
 Rods _____
 Additional Information
Run 8" casing & cemented to top SL 426.
5 B. W. P. W. from 500 to 510. S. L.
1. 700'. 18 BWPH 687-692. SL 728.
Clean out. Run 735' of upset & cement
with 3 sacks of cement & 1 sack of cement
ium. SLM outside of 2" 728' (inside
770'). Run 3 more sacks of cement.
250' of water outside of 2". Run
35 joints of 1" & cemented with 3
sacks. Pull 1". Run SLM. Later
went to 715 outside 2". Pull 7".
Run tubing & rods.