

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

IMPORTANT
Kans. Geo. Survey request samples on this well.

State Geological Survey


WICHITA BRANCH

S. 30 T. 15 R. 20 E

Loc. 825' FEL & 495' FNL

County Franklin 4812 FSL: 679 FEL

640 Acres



1
KCC
record

Elev.: Gr. _____

DF _____ KB _____

API No. 15 — 059 — 21,185
County Number

Operator
P & W Oil

Address
5987 Miller Arvada, Colo 80004

Well No. #BBR 2 Lease Name Bleakley/Brady

Footage Location 495 4812 FSL: 679 FEL - 1000 825
feet from (N) line feet from (E) line

Principgl Contractor P & W Drilling Geologist none

Spud Date 5/27/80 Date Completed 5/30/80 Total Depth 825' P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser LaJet, Inc.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	8 1/8	6 1/4	17#	25	Neet	1	
production	5 1/4	2 3/8	3.75	780	Portland A	110	2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			25	1 11/16 glasjets	762-774

Size	Setting depth	Packer set at
2 3/8	780'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
8 sx 12-30 sand	762-774
20 sx 10-20 sand	
60# water gel	

INITIAL PRODUCTION

Date of first production 7-1-80	Producing method (flowing, pumping, gas lift, etc.) pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 1 bbls. Gas 0 MCF Water 0 bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) na	Producing interval (s) 762-774

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans- mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No.	Lease Name	
S	T	R
		E
		W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<i>see attached log</i>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 _____ Signature
	 _____ Title
	7/21/81 _____ Date

30-15-20E

Farm - Brady

Contractor - P & W Drilling

County - Franklin

Drilling Started -

Well - BBR 2

Drilling Completed -

Lease Owner - P&W

Permanent Casing

<u>Size</u>	<u>Amount</u>	<u>Condition</u>	<u>Cement</u>
-------------	---------------	------------------	---------------

Strata

Total Depth

Soil & Clay	5	
Yellow Clay	15	
Slate	21	
Lime	76	
Shale	130	
Lime	140	
Shale	200	
Sand	212	
Shale & Shells		
Lime	235	
Shale & Shells	245	
Lime	276	
Shale	300	
Lime	305	
Shale	316	
Lime	400	
Shale	445	
Lime	446	
Shale	471	
Lime	625	
Shale	634	
Lime	670	
Shale	676	
Lime	681	
Shale & Shells	702	
Lime Shells	724	
Shale	727	
Lime	730	
Shale & Shells	741	
Lime	742	
Sand	759	
Shale	762	
Oil Sand	774	
Shale	825	T.D.