

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION OR RECOMPLETION FORM
ACO-1 WELL HISTORY
DESCRIPTION OF WELL AND LEASE

03625

Operator: License #
Name RODNEY WISE
Address 1810 hunting Ave. #2
Manhattan, Kansas 66502
City/State/Zip

Purchaser UNKNOWN
.....

Operator Contact Person RODNEY WISE
Phone 913-537-8877

Contractor: License # 8509
Name EVANS ENERGY DEVELOPMENT

Wellsite Geologist NCNE
Phone

Designate Type of Completion

☒ New Well ☐ Re-Entry ☐ Workover
☒ Oil ☐ SWD ☒ Temp Abd
☐ Gas ☐ Inj ☒ Delayed Comp.
☐ Dry ☐ Other (Core, Water Supply etc.)

If ONWQ: old well info as follows:

Operator
Well Name
Comp. Date Old Total Depth

WELL HISTORY

Drilling Method:

☒ Mud Rotary ☐ Air Rotary ☐ Cable
9-25-87 10-2-87
Spud Date Date Reached TD Completion Date
1051 none
Total Depth PBTD

Amount of Surface Pipe Set and Cemented at 140.8 feet
Multiple Stage Cementing Collar Used? Yes ☒ No
If yes, show depth set feet
If alternate 2 completion, cement circulated
from 1005 feet depth to surface 150 SX cmt
Cement Company Name CONSOLIDATED
Invoice # 80229

SIDE ONE

API NO. 15-045-21,011
County Douglas
SE SW SE Sec. 6 Twp. 15 Rge. 21 ☒ East
..... West

390 359 FSL and 1358 FEL SW SW SE -KCC Record
1340 Ft North from Southeast Corner of Section
..... Ft West from Southeast Corner of Section
(Note: Locate well in section plat below)


Lease Name Chuck Wise Well # 1

Field Name Baldwin City

Producing Formation Cattlemans

Elevation: Ground 1040 KB

Section Plat



WATER SUPPLY INFORMATION

Disposition of Produced Water: _____ Disposal
Docket # _____ Repressuring

Questions on this portion of the ACO-1 call:

Water Resources Board (913) 296-3717

Source of Water:
Division of Water Resources Permit #

Groundwater Ft North from Southeast Corner
(Well) Ft West from Southeast Corner of
Sec Twp Rge East West

Surface Water Ft North from Southeast Corner
(Stream, pond etc) Ft West from Southeast Corner
Sec Twp Rge East West

Other (explain)
(purchased from city, R.W.D. #)

INSTRUCTIONS: This form shall be completed in triplicate and filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 120 days of the spud date of any well. Rule 82-3-130, 82-3-107 and 82-3-106 apply.
Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form. See rule 82-3-107 for confidentiality in excess of 12 months.
One copy of all wireline logs and drillers time log shall be attached with this form. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

SIDE TWO

Operator Name Rodney J. Wise Lease Name Chuck Wise Well # 1
 Sec. 6 Twp. 15s Rge. 21 ☒ East ☐ West County Douglas

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☐ Yes ☒ No
 Samples Sent to Geological Survey ☒ Yes ☐ No
 Cores Taken ☐ Yes ☒ No

Formation Description
☐ Log ☐ Sample

Name Top Bottom

Copy of log on back

CASING RECORD ☒ New ☐ Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	10 1/4"	7"		140	oil well	150	
Production	6 1/4"	4 1/2"		1005	bulk	130	

PERFORATION RECORD		Acid, Fracture, Shot, Cement Squeeze Record	
Shots Per Foot	Specify Footage of Each Interval Perforated	(Amount and Kind of Material Used)	Depth

TUBING RECORD			
Size	Set At	Packer at	Liner Run ☐ Yes ☐ No

Date of First Production	Producing Method
	☐ Flowing ☐ Pumping ☐ Gas Lift ☐ Other (explain).....

Thickness
of Strata

Formation
Soil & Clay

Total

6-15-21E

6	Soil & Clay	6
28	Sandstone	34
16	Sand	50
6	Shale	56
24	Sand	80
60	Sand	140
2	Lime	142
17	Sand	159
6	Lime	165
28	Sand	183
20	Shale	203
5	Lime	208
3	Shale	211
16	Lime	227
8	Shale	235
9	Lime	244
7	Shale	251
23	Lime	274
10	Shale	284
6	Lime	290
5	Shale	295
15	Lime	310
70	Shale	380
4	Lime	384
3	Shale	387
18	Lime	405
17	Shale	422
10	Lime	432
17	Shale	449
17	Lime	466
8	Shale	474
3	Lime	477
13	Shale	390
25	Lime	515
6	Shale	521
25	Lime	546
3	Shale	549
16	Lime	565
6	Shale	571
4	Sand	575

Brown & Brwon Clay

Brown

Brown

White

White Good Water

White hard limey

Hertha

White

White

Gray

White

Set 140.80' 7" surface casing
Set 1005.5' 4½" casing

Chuck Wise #1

15-045-21011

8-15-21E
565