

KANSAS DRILLERS LOG

API No. 15 — 059 — 20,661
County Number

Operator

Erie Oil Co.

Address

Box 63 Wellsville, Kansas 66092

Well No.

#14

Lease Name

Coons

Footage Location

feet from (N) (S) line

3965 FSL: 4120 FEL-1CCC

feet from (E) (W) line

Principal Contractor

J & J Drilling

Geologist

Spud Date

26 Nov 78

Total Depth

762

P.B.T.D.

Date Completed

29 Nov 78

Oil Purchaser


Square Deal

S. 32 T. 15 R. 21 E W

Loc. 1800' FWL & 825' FSL NW

County Franklin

SE NW NW

640 Acres
N

Locate well correctly

Elev.: Gr.

DF

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		6 1/4		21.35	Portland	4	
Tubing	5 1/8	2		762	Portland	90	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		712-725
TUBING RECORD					
Size	Setting depth	Packer set at			
2	762				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
50 gal acid, 110 bbls water w/30 sacks sand	712-725

INITIAL PRODUCTION

Date of first production 2 May 79	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 5 bbls. Gas MCF 5 bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) vented	Producing interval (s) 712-725

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

32-15-21 E

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Oil

Operator

John E. Casady

Well No.

15

Lease Name

Coons

S 32 T 15 R 21 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
soil	0	2		
clay	2	17		
shale sandy	17	55		
lime	55	80		
shale	80	90		
lime soft	90	120		
shale	120	170		
lime	170	180		
shale	180	255		
lime	255	285		
shale	285	295		
lime	295	305		
shale limey	305	360		
lime	360	385		
shale	385	400		
lime	400	430		
shale	430	435		
lime	435	440		
shale sandy	440	550		
lime	550	585		
shale limey	585	610		
shale black	610	618		
lime	618	624		
shale black	624	628		
lime	628	652		
shale limey	652	660		
lime	660	668		
shale limey	668	673		
lime broken	673	686		
shale black	686	691		
brown lime and shale	691	696		
shale and lime	696	710		
oil sand	710	727		
broken sand	727	734		
shale limey	734	762		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Title

Date