

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 059-21 — 231
County Number

Operator

John T Casady

Address

Box 63 Wellsville KS

Well No.

24

Lease Name

Moldenhauer

Footage Location

165 6050 FSL & 4904 FSL 495
feet from (N) line feet from (W) line

Principal Contractor

Casady Drilling

Geologist

—

Spud Date

31 Jul 80

Date Completed

1 Aug 80

Total Depth

760

P.B.T.D.

— 742

Directional Deviation

—


Oil and/or Gas Purchaser

Square Deal Oil Co

State Geological Survey
WICHITA, BRANCHS. 32 T. 15 R. 21 E
Loc. APPX C NE NW NW
County Franklin NG NW NW
NW
1600

640 Acres

N



Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8"	7"		45	portland	4	—
Casing	5 1/4"	2"	3.5	742	portland	90	—

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1		725-735
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
50 gal acid, 30 sacks sand w/ ~ 80 bbls H ₂ O	725-735

INITIAL PRODUCTION

Date of first production 30 Aug 80		Producing method (flowing, pumping, gas lift, etc.) Pump			
RATE OF PRODUCTION PER 24 HOURS		Oil 3	Gas bbls.	Water 7 MCF	Gas-oil ratio bbls. CFPB
Disposition of gas (vented, used on lease or sold) Vented				Producing interval(s) 725-735	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

JOHN T. CASADY

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

OIL

Well No.

24

Lease Name

MOLDENHAWER

S 32 T 15 R 21 E

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil & Clay	0	17		
Shale	17	40		
Lime	40	85		
Shale	85	97		
Lime	97	102		
Shale	102	104		
Lime	104	127		
Shale	127	172		
Lime	172	192		
Shale	192	270		
Lime	270	312		
Shale	312	353		
Lime	353	356		
Shale	356	373		
Lime	373	430		
Lime	430	447		
Shale	447	600		
Shale w/lime shells	600	670		
Shale	670	675		
Lime, some shale	675	688		
Shale	688	719		
Broken sand	719	720		
Oil sand w/laminat.	720	724		
oil sand	724	729		
white sand	729	730		
Laminated sand	730	733		
Shale	733	740		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Title

9 Nov 80

Date