

INSTRUCTIONS: Within 30 days after completion of this well the owner or operator should complete the form and mail it to Margaret Oros, Chairman, AAPG-CSD District 12, State Geological Survey of Kansas, Lindley Hall, Lawrence, Kansas 66044, in the enclosed stamped, self-addressed envelope. (The information given in the IBM print-out is taken from the "Intents-to-Drill" list of the Oil and Gas Conservation Division of the State Corporation Commission of Kansas, 500 Insurance Building, Wichita, Kansas 77602. Please correct any item that is in error.)

*Miami*  
W.W. George #1 Faust  
Farm

\*\*\*\*\*

Date Drilling Began: 2-15-69

Date Drilling Completed: 3-5-69

Hole completed as (check): Dry ;

Oil ; Gas ; Service well

Total depth of hole: 505 Ft

Name of formation at total depth: Perm sand

If OWWO\*, give new footage drilled: \_\_\_\_\_

Field Name: W.W. George Farm

Name of Company purchasing oil or gas: \_\_\_\_\_


Initial Potential or Production: \_\_\_\_\_ Barrels of oil/day \_\_\_\_\_;

Barrels of water/day \_\_\_\_\_; Thousand cu ft gas/day 80,000

Oil Gravity \_\_\_\_\_ °API; Pay Depth (Bottom) 505

Net Pay Thickness 6 Ft.; Name of Pay Zone Perm sand

Please show location of well in section:



Elevation: Derrick floor Don't know

Kelly Bushing \_\_\_\_\_ Ground \_\_\_\_\_

Electric or other logs were run: Yes \_\_\_\_\_ No

Well was Cored: Yes \_\_\_\_\_ No

Drill Stem Test Run: Yes \_\_\_\_\_ No

Please use other side of sheet for additional information. Copy of driller's log, electric logs, and other well information would be appreciated. (\* OWWO - Old hole re-worked or deepened.)

The AAPG's Committee on Statistics of Drilling (CSD) on January 1, 1966 began compiling data on wells reported drilled in the U. S., Canada, and Mexico. The Oil and Gas Journal has contracted to publish weekly statistical summaries of the data. These will be used by the International Oil Scouts Assoc. American Petroleum Inst., U. S. Bureau of Mines, and other groups, and will be considered the official source of drilling information by the U. S. Department of the Interior.

Many of the wells drilled in southeastern Kansas are not presently scouted. Because of this the CSD District 12 Chairman is sending this Well Completion Report form to all operators who have stated their intent to drill a well. The information received will also be placed on open file in the Oil and Gas Division offices of the State Geological Survey of Kansas. The operation of all of the operators in returning the completed form will be greatly appreciated.

led with  
ole tool rig

**CARL MOORE**  
**DRILLING CONTRACTOR**  
Oil - Gas - Water  
Phone TU 3-6282  
Wellsville, Kansas 66092

36-15-21 E  
~~NE SW SW~~  
NW SW SE (?) (KCC)  
Intent  
March 7, 1969

Faust #1

LOG ON GAS WELL ON W.W.GEORGE FARM.SEC.36,TWP.15,R.21.

MIAMI COUNTY

7	Soil	7	
25	Lime	32	
20	Shale	52	Run 2 inch tubing with 6/8 packer on bottom, packer set at 497 1/2 with 7 1/2 ft. of anchor under packer, run 4 sacks cement on packer.
25	Lime	77	
83	Shale sandy	160	
23	Lime	183	
32	Shale sandy	215	
5	Lime	220	22 ft. of 6/8 drive pipe in top of hole.
50	Shale	270	
25	Lime	295	Hole filled with Gel to surface.
2	Slate (black)	297	
5	Shale (black)	302	
23	Lime	325	
3	Slate (black)	328	Little water, 3 bailers overnight, 16 hrs.
19	Lime (hertha)	347	
20	Shale	367	
25	Shale (light)	392	
58	Shale (gray)	450	Set 491 ft. of 7 inch pipe over sand, pulled after well was drilled in.
49	Shale (light sandy)	499	
2	Sand	501 (Gas)	
3	Sand (hard)	504	
1	Sand (soft)	505 (Gas)	
		505	Total Depth