

2-15-24 E *Plotted*

Company A. C. Higgins

Sec. 2 T. 15 R. 24 E
Loc. SW NE SE

Farm Baker

No. 2

Total Depth 542

County Johnson


Comm.

Comp.

Shot or Treated

Contractor

Issued



Casing

20 in.

10 in.

15 1/2

8 1/4

12 1/2

6 5/8

13 3/8

5 3/16

Elevation 1054

Production 124,000 CFg

Figures Indicate Bottom of Formation

soil	4
clay	14
lime water at 60'	98 Iola
shale blue	120 water
lime white	128
shale blue	140
lime	142
shale blue	163
lime	168
shale blue	175
shale light	194
shale blue	220
lime	245 Winterset
shale dark	252
lime	274 Bethany Falls
shale blk	278
lime gray	281
shale blue	283
lime	292 Hertha
shale	306 Gas showing
Broken sand	338 Gas oil showing <i>Knobrow</i>
shale blue	350
shale light	365
shale sandy	379
shale blue	407
shale light	424 Water
shale light	438
shale blue	446
shale pink	480
shale light	483
lime	487
shale	490
lime	492
shale light	497
lime	502
shale light	508
shale sandy	513
shale dark	521
lime	527
shale sandy	538
lime	542

Total Depth.

Open flow test August 1,
1930 124,000 cu. ft. 90 lbs. R.P.