


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. E.H. ADAIR OIL CO.
Farm. Clark No. 1

SEC. 7 15 R. 6E
SW SW NW

Total Depth. 2385'
Comm. 2-25-60 Comp. 3-9-60
Shot or Treated.
Contractor. Eureka Drilling Co.
Issued. 4-23-60

County Morris
KANSAS



CASING:
8 5/8" 208' cem. w/120 sx.

Elevation. 1423 RB

Production. Dry

Figures Indicate Bottom of Formations.

surface hole to	208
shale & lime	1400
lime	1421
Black shale	1425
lime	1463
shale	1473
sand	1499
shale	1561
lime	1564
shale	1618
lime	1708
shale	1731
lime	1762
shale	1768
lime	1793
shale	1798
lime	1883
Black shale	1887
lime	1914
Black shale	1917
lime	1947
shale	2007
lime & shaley lime	2122
cherty lime	2129
conglomerate	2153
chert	2172
lime	2217
sandy dolomite	2232
shale	2369
dolomite	2385
Total Depth	

TOPS:

Heebner Shale	1421
Douglas Sand	1463
Lansing	1618
Base Kansas City	1947
Pennsylvania Conglomerate	2129
Mississippi Chert	2153
Mississippi Lime	2172
Kinderhook Shale	2232
Hunton Dolomite	2369

DST #1 2153-73: Open 1½ hrs. w/
weak blow. Recovered 50" slightly
oil-cut watery mud.
ISIP - 740# in 20 minutes.
FSIP - 610# in 30 minutes.
No flow pressures.