

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


24-15-8E ✓

Company- E. H. ADAIR OIL & D. R. LAUCK
Farm- Cosgrove No. 1

SEC. 24 T. 15 R. 8E
SW NE SE

Total Depth. 3203'
Comm. 8-13-65 Comp. 8-24-65
Shot or Treated.
Contractor. Abercrombie Drlg.
Issued. 10-9-65

County Morris
KANSAS



CASING:

Elevation. 1447' KB

8 5/8" 180' cem w/ 115 sx

Production. DRY

Figures Indicate Bottom of Formations.

shale & lime	1020
shale	1152
lime & shale	1420
shale	1648
lime	1720
shale	1770
lime	2007
shale	2103
lime	2276
shale	2456
shale & lime	2566
sand	2570
lime & chert	2813
shale	2942
Dolomite	3118
shale	3196
Dolomite	3202
Total Depth	

TOPS: SMP

Lansing	1648
Kansas City	1770
Base Kansas City	2007
Burgess	2566
Mississippi	2570
Kinderhook	2813
Hunton	2942
Maquoketa	3118
Viola	3196

DST # 1 3195-3203 Op 45 min. Rec. 2220
sulfur water. IBHP 980# 20 min; FBHP 980#
30 min; IFP 417#, FFP 980#.