

KANSAS

15-127-20307

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 127 — 20,307
County Number

Operator

Exxon Corp.

Address

P. O. Box 1600 Midland, Texas 79702

Well No.

#8

Lease Name

Lucy B. Kieffer

Footage Location

995 feet from (N) line 1630

4950 FSL and 3630 FEL-KCC Record

feet from (E) line

Principal Contractor

B+N DRILLING CO.

Geologist

Spud Date

6-14-79

Date Completed

6-21-79

Total Depth

3173

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

EXXON CORPORATION

Loc. 995' FNL & 1630' FEL


4950 FSL and 3630 FEL-KCC

County Morris

Record

640 Acres

N



Locate well correctly

Elev.: Gr. 1400

DE 1407 KB 1408

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 1/4	8 5/8	24* K-55	220	Class A	200	2% CACL
PRODUCTION STRING	7 7/8	5 1/2	14* K-55	3072	CLASS A	95	10% SALT + 2% CACL

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

OPEN HOLE

Size	Setting depth	Packer set at
2 7/8	3055	—

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
NONE OPEN HOLE COMPLETION 3072-3073	

INITIAL PRODUCTION

Date of first production 7-6-79		Producing method (flowing, pumping, gas lift, etc.) PUMPING 2 1/2" x 1 1/2" x 14'			
RATE OF PRODUCTION PER 24 HOURS	Oil 225	Gas bbls. 0	Water MCF 0	Gas-oil ratio bbls. 0 CFPB	
Disposition of gas (vented, used on lease or sold) NONE			Producing interval (s) 3072-3073		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 8	Lease Name LUCY B. KIEFFER	OIL
S 26 T 15 R 9 E		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Rock	0	15		
Rock, Lime, shale	15	190		
Rock + shale	190	223		
Shale + Rock	223	318		
Shale + Lime	318	690		
Lime + shale	690	1115		
Shale + Lime	1115	1405		
Lime + shale	1405	1618		
Lime	1618	1804		
Lime + shale	1804	1965		
Lime + shale	1965	2100		
Lime	2100	2275		
Lime + shale	2275	2460		
Lime	2460	2620		
Lime	2620	2686		
Lime + shale	2686	2726		
Lime + shale	2726	2870		
Lime	2870	3050		
Shale + Lime	3050	3173	TD	

Log - Schlumberger FDC, GR, DL + caliper logs

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature A L Cloninger
	UNIT HEAD
	Title
	Date 7-9-79
	Date 7-13-79