


PHIL-HAN OIL & ADAIR-MORTON CO.
Eggleston No. 1.

SEC. 31 T. 16 R. 1 E
SE 1/4 SW

59014

Total Depth. 2720'
Comm. 3-26-43 Comp. 4-6-43
Shot or Treated.
Contractor. Veeder Sup&Dev Co.
Issued. 4-17-43

County. Dickinson



CASING:
8 5/8" 167' Cen.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

soil & clay	0-20
shale	40
gravel, shale, lime	50
shale	105
shelly lime & shale	142
lime brkn	160
set surface pipe	
cement & plug	140-160
lime & shale	160-170
lime sdy	220
shale & lime hd	255
lime sdy	270
red rock & shale	290
sand, lime & shale	390
red bed	405
lime, sand	445
shale, lime	530
shale sticky	580
red rock	590
shale & shells	605
sand & lime	650
lime & shale	750
shale shells	805
lime & shale	905
sand & shale	930
shale & lime shells	1080
red rock & shale	1090
shale, shells	1260
lime, sticky shale	1300
shale & lime shells	1505
sand & shale	1535
lime & shale	1685
shale sdy	1710
lime	1770
lime & shale	1910
sdv shale & lime	1987
shale brown lime	2015
shale lime	2055
lime-K.C.	2090
lime K.C. & shale	2160
lime & shale	2290
sdv lime & shale	2375
lime & shale	2575
lime brkn	2610
shale & lime shells	2706
chat	2720
Total Depth.	

Tops: Lansing 2690
Chat 2706