

State **Kansas** County **Osage**

Company **Messman-Rinehart Oil Co.** Well No. **1**


Farm **Neill**

Survey

Block No. Sec. **15** Twp. **16 S.** Range **16 E**

Co-Ord. Elev. **1021' Gr**
1025' R/B

App. **SE SE NE** Contr. - **Eureka Drlg. Co.**



- 25% - A. A. Seeligson, Jr.
- 12.5% - A. A. Seeligson, Sr.
- 6.25% - Josephine L. Gill
- 6.25% - Richard Gill
- 12.5% - Collins-Hughes
- 12.5% - Chicago Group
- 25% - Messman-Rinehart Oil Co.
- ORI - Huntsman Haworth
- 1650' Miss. test

NOTE: Show Sketch of Lease and Well Location in Above Space

27

Ft. from N. Line **280** Ft. from S. Line

Ft. from W. Line **300** Ft. from E. Line

Date	Depth	
6/28/61		Spud - 7" @ 105' w/30 sx.cem.
		P.D. @ 2:00 p.m. 6/28/61
6/29		S.U.S. (2:00 a.m.)
6/29	440	Drlg.
6/30	1100	Drlg.
7/1	D.S.T. #1	- 1370-80' - 0p 1 hr.,
		wk. bl., Rec. 15' mud,
		BHP 485#, FP 5-18#, HHd 650#
	1461	Burgess Sand (-436)

Date	Depth	
	1470	Miss. Chat (-445)
	1519	Miss. Lim (-494)
Core #1	- 1463-83'	(19') Rec. 16') bleeding oil
Core #2	- 1483-08'	(25') Rec. 19')
		Dolo. 1484-98'
	1543	Drig.
	1545	R.T.D.
		4 $\frac{1}{2}$ " @ 1545' w/40 sx. cem.
		P.D. @ 3:00 a.m. 7/4/61
7/11		M.I.C.T.
		Perf. 1493-96' w/4 ^s ft.,
		Treated w/800 gal. acid,
		Max. pr. 500#, fed in @ 25
		gal/min., Set 45 ^m , bled off
		to 10# in 5", no vac.
		Set overnight - fillup 300'
		Swbd. 5 BF (1/2 oil-1/2 wtr.)
		in 2 hrs., Swbd. 1 $\frac{1}{2}$ BF-
		1/2 oil in 1 hr., Swb. 1 BF
		1/2 oil in 1 hr.
7/17		SI 4 da., swbd. 1 bbl. oil
		& 16 bbls. acid wtr., Treated
		w/2000 gal. kerosene - went in
		max. 500# at rate of 5 BF-
		per min., treated

896169

State Kansas County Osage

Company Messman-Rinehart Oil Co. Well No. 1


Farm Neill

Survey _____

Block No. _____ Sec. 15 Twp. 16 S Range 16 E

Co-Ord. _____ Elev. 1025' R/B

App. SE SE NE



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

22

Ft. from N. Line

280

Ft. from S. Line

Ft. from W. Line

300

Ft. from E. Line

Date	Depth	
		w/3000 gal. acid, max. pr
(Total load 162 bbls.)		700#, went in at rate of 5 BF/min., at end of 10"
		bled off to 200# (did not go on vac.), Swb. 5 BFPH (had 53 bbls. back)
7/18		Swbd. 102 BF (est. 75 BW & 27 BO) at rate of 5 BFPH
		(15% oil - 85% wtr.)

